



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

11712
 11594

TICKET NUMBER 55915
 LOCATION Ogley #
 FOREMAN Miles Sta

FIELD TICKET & TREATMENT REPORT
 CEMENT **Invoice #814242** KS

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
9-25-18	7158	Michaelis #4	3	14 S	32 W	Leaqua	
CUSTOMER Raymond oil			Gopher us Shomshans Rd 1/2 mi S of into				
MAILING ADDRESS P.O. Box 48788							
CITY Wichita		STATE KS	ZIP CODE 67201				
TRUCK #		DRIVER		TRUCK #		DRIVER	
731		WELLD					
B307429		WELLD					
705		MILES					

JOB TYPE Surface HOLE SIZE 12.25" HOLE DEPTH 203 CASING SIZE & WEIGHT 8 5/8" x 24#
 CASING DEPTH 240' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.8 SLURRY VOL 1.36 WATER gal/sk _____ CEMENT LEFT in CASING 20'
 DISPLACEMENT 15.5 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting and Rig upon L.D. drilling circulate casing
mix 175SX Surface blend II displac 15.5 bbls water Shut in cemented and
circulate 3 bbls bit

Thanks Miles & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0470	1	PUMP CHARGE	1150.00	1150.00
CE0007	25	MILEAGE	7.15	178.75
CE0711	8.22 TONS	Ton Mileage delivery	660.00	660.00
CE5871	175 SX	Surface blend II	24.00	4200.00
Sub Total			6188.75	6188.75
less 25% discount				1547.19
Subtotal				4641.56
SALES TAX				252.00
ESTIMATED TOTAL				4893.56

AUTHORIZATION Leonard Boese TITLE Driller DATE 9-25-18

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

11803
11087

TICKET NUMBER 55880
LOCATION Oakley Ks
FOREMAN Walt Dunkel
miles Shaw
Ks

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 819342

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-6-18	7158	Michaelis #4	3	14 ^s	32 ^u	Logan
CUSTOMER Raymond Oil Co			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. BOX 48788			753	Cory Wilson		
CITY Wichita			5301/T127	Neil White		
STATE KS			5301/T129	Steve Clinesmith		
ZIP CODE 67201			691	Walt Dunkel	703	Miles Shaw
JOB TYPE	HOLE SIZE	HOLE DEPTH	CASING SIZE & WEIGHT			
Prod	7 7/8	4642'	4 1/2 10.5			
CASING DEPTH	DRILL PIPE	TUBING	OTHER			
4641			DV 2 2360			
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING			
14.2/12.5			21.08			
DISPLACEMENT	DISPLACEMENT PSI	MIX PSI	RATE			
			6 BPM			

REMARKS: Safety Manning, rig up on L D Digs, Circ casing on bottom,
Pump 500 gal mud flush, mix 300 sks Thixobland II, clear Pump lines, release
Plug & Displace 40 BBL water + 4 3/4 BBL mud @ 1000#, Landed @ 1700#
released Pressure, Float Held, Open DV Tool, Circ For 1 Hr,
mixed 30 sks Lite Cement in BH, mixed 470 sks cement, clear Pump Lines
release Plug, Displace 3 6/8 BBL H2O @ 800#, Shut tool @ 2000#
released Pressure, Tool Held
Cement Did Circ
Thank You
Walt & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
Ceo 453	1	PUMP CHARGE	2,800.00	2,800.00
Co0002	25	MILEAGE	7.15	178.75
Ceo 710	35.60	Ton Mileage Delivery	1.75	1,557.50
CC5862	300 sks	Thixobland III	26.00	7800.00
CC6077	1500#	Kolseal	1.50	750.00
CC5831	500 - sks	Lite Weight Blend VII	17.50	8,750.00
CC6075	125 - #	Flo-Seal	3.00	375.00
CC6125	500 gal	mud flush	1.65	325.00
CP8484	1	4 1/2 Float shoe	470.00	470.00
CP8253	1	4 1/2 Latch down Plug assembly	340.00	340.00
CP8575	9	4 1/2 Turbolicizers	95.00	855.00
CP8628	2	4 1/2 Baskets	350.00	700.00
CP8800	1	4 1/2 DV Tool	5,040.00	5,040.00
				29,941.25
			Less 25%	7,485.31
				22,455.94
			SALES TAX	1524.30
			ESTIMATED TOTAL	23,980.24

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.