



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-457-8678

12042
11922

TICKET NUMBER 55536
LOCATION Ottawa, KS
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

INVOICE #814581

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11/16/18	2890	Dart et al # 8-21	NF 20	27	16	WL
CUSTOMER Domestic Energy Partners			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS PO Box 296			503 / Casken ✓ Safety Meeting			
CITY STATE ZIP CODE Fredonia KS 66736			495 / Har Bec ✓			
			702 / Brad Butler			

JOB TYPE long string HOLE SIZE 6 3/4" HOLE DEPTH 1212' CASING SIZE & WEIGHT 4 1/2"
CASING DEPTH 1211 DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 13.5# SLURRY VOL 41 bbls WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 19.31 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100 # Caustic Soda followed by 15 bbls fresh water, mixed + pumped 130 sks Thixobland II cement w/ 5# Kalseal + 1/2# Pheno seal per sk, flushed pump clean, pumped 4 1/2" rubber plug to casing TD w/ 19.31 bbls water, pressured to 800 PSI, well held pressure, release pressure to set float valve.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	65 mi	MILEAGE	464.75	
CE0711	min	ten mileage	1600.00	
		trucks	2624.75	
		- 25%	656.19	
		Subtotal		1918.56
CC5861	130 sks	Thixobland II cement	3510.00	
CC6074	650 #	Kalseal	325.00	
CC6079	65 #	Pheno seal	87.75	
CC6151	100 #	Caustic Soda	200.00	
CP8178	1	4 1/2" rubber plug	75.00	
		materials	4197.75	
		- 25%	1049.44	
		Subtotal		3148.31
		6.5%		204.64
		SALES TAX		204.64
		ESTIMATED TOTAL		5321.51
				(7095.35)

SCANNED

AVIN 3737 AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.