

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form U3C  
June 2015  
Form must be Typed  
Form must be completed  
on a per well basis

**ANNUAL REPORT OF PRESSURE MONITORING,  
FLUID INJECTION AND ENHANCED RECOVERY**

Complete all blanks - add pages if needed. Copy to be retained for five (5) years after filing date.

OPERATOR: License # \_\_\_\_\_  
Name: \_\_\_\_\_  
Address 1: \_\_\_\_\_  
Address 2: \_\_\_\_\_  
City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_ + \_\_\_\_\_  
Contact Person: \_\_\_\_\_  
Phone: ( \_\_\_\_\_ ) \_\_\_\_\_  
Lease Name: \_\_\_\_\_  
Well Number: \_\_\_\_\_

API No.: \_\_\_\_\_  
Permit No.: \_\_\_\_\_  
Reporting Year: \_\_\_\_\_  
(January 1 to December 31)  
\_\_\_\_ - \_\_\_\_ - \_\_\_\_ - \_\_\_\_ Sec. \_\_\_\_ Twp. \_\_\_\_ S. R. \_\_\_\_  E  W  
(a/a/a/a)  
\_\_\_\_\_ feet from  N /  S Line of Section  
\_\_\_\_\_ feet from  E /  W Line of Section  
County: \_\_\_\_\_

**I. Injection Fluid:**

Type (Pick one):  Fresh Water  Treated Brine  Untreated Brine  Water/Brine  
Source:  Produced Water  Other (Attach list)  
Quality: Total Dissolved Solids: \_\_\_\_\_ mg/l Specific Gravity: \_\_\_\_\_ Additives: \_\_\_\_\_  
(Attach water analysis, if available)

**II. Well Data:**

Maximum Authorized Injection Pressure: \_\_\_\_\_ psi Injection Zone: \_\_\_\_\_  
Maximum Authorized Injection Rate: \_\_\_\_\_ barrels per day  
Total Number of Enhanced Recovery Injection Wells Covered by this Permit: \_\_\_\_\_ (Include TA's)

III.	Month:	Total Fluid Injected BBL	Maximum Fluid Pressure	Total Gas Injected MCF	Maximum Gas Pressure	# Days of Injection
	January	_____	_____	_____	_____	_____
	February	_____	_____	_____	_____	_____
	March	_____	_____	_____	_____	_____
	April	_____	_____	_____	_____	_____
	May	_____	_____	_____	_____	_____
	June	_____	_____	_____	_____	_____
	July	_____	_____	_____	_____	_____
	August	_____	_____	_____	_____	_____
	September	_____	_____	_____	_____	_____
	October	_____	_____	_____	_____	_____
	November	_____	_____	_____	_____	_____
	December	_____	_____	_____	_____	_____
	<b>TOTAL</b>	_____	_____	_____	_____	_____

## Complete Water Analysis Report

Customer: SHAKESPEARE OIL COMPANY  
 Region: Kansas  
 Location: Lane County  
 System: Production System

Equipment: Keenan Stucky 1-34  
 Sample Point: Bleeder  
 Sample ID: AQ70666  
 Acct Rep Email: Michael.Walters@championx.com

Collection Date: 02/10/2021  
 Receive Date: 02/10/2021  
 Report Date: 02/11/2021  
 Location Code: 430667

### Field Analysis

Bicarbonate	215 mg/L	Dissolved CO2	185 mg/L	Dissolved H2S	146 mg/L
Pressure Surface	25 psi	Temperature	100 ° F	pH of Water	7.5

### Sample Analysis

Conductivity (Calculated)	77740 µS - cm3	Ionic Strength	0.91 mol/L	Resistivity	0.129 ohms - m
Specific Gravity	1.039	Total Dissolved Solids	49753.92 mg/L		

### Cations

Iron	<0.1 mg/L	Manganese	<0 mg/L	Barium	0.257 mg/L
Strontium	30.96 mg/L	Calcium	825.0 mg/L	Magnesium	309.7 mg/L
Sodium	17660.00 mg/L				

### Anions

Chloride	27675 mg/L	Sulfate	3038 mg/L
----------	------------	---------	-----------

### Scale Type

Anhydrite CaSO4 PTB	N/A	Anhydrite CaSO4 SI	-0.65
Barite BaSO4 PTB	0.1	Barite BaSO4 SI	0.49
Calcite CaCO3 PTB	5.8	Calcite CaCO3 SI	0.05
Celestite SrSO4 PTB	N/A	Celestite SrSO4 SI	-0.02
Gypsum CaSO4 PTB	N/A	Gypsum CaSO4 SI	-0.51
Hemihydrate CaSO4 PTB	N/A	Hemihydrate CaSO4 SI	-0.49

### Comments

Scaling predictions calculated using Odco-Tomson model

This document contains the confidential and/or proprietary information of ChampionX. The recipient agrees to maintain the confidentiality of the terms of this document, and shall not reproduce it by any means, disclose the contents of it to any third party, or use the contents of it for any purpose other than the purpose for which it was intended by ChampionX.