

GLOBAL OIL FIELD SERVICES, LLC

0013249

REMIT TO 24 S. Lincoln
Russell, KS 67665

SERVICE POINT:
RUSSELL, KS

DATE <u>11-10-18</u>	SEC. <u>23</u>	TWP. <u>14</u>	RANGE <u>16W</u>	CALLED OUT <u>2 PM</u>	ON LOCATION <u>5 PM</u>	JOB START <u>6 PM</u>	JOB FINISH <u>6:45 PM</u>
LEASE <u>FURTHMYER</u>		WELL #. <u>4</u>	LOCATION <u>WALKER, KS 2 SOUTH, 1/2 EAST.</u>			COUNTY <u>ELLIS</u>	STATE <u>KS</u>
OLD OR NEW (CIRCLE ONE)							

CONTRACTOR WHITE KNIGHT DRILLING
 TYPE OF JOB SURFACE
 HOLE SIZE 12 1/4 T.D. 217.32
 CASING SIZE 8 5/8 DEPTH 207.32 + 10' LT
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2" XH DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 43.34'
 CEMENT LEFT IN CSG. 20'
 PERFS _____
 DISPLACEMENT 12 1/2 BBL
 EQUIPMENT _____

PUMP TRUCK CEMENTER BRAND
 # 409 HELPER JASON
 BULK TRUCK _____
 # 379 DRIVER TOM
 BULK TRUCK _____
 # _____ DRIVER _____

OWNER _____
 CEMENT AMOUNT ORDERED 150 SK COM 3% CC 2% GEL
 COMMON _____ @ _____
 POZMIX _____ @ _____
 GEL _____ @ _____
 CHLORIDE _____ @ _____
 ASC _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING _____ @ _____
 MILEAGE _____ @ _____
 TOTAL _____

REMARKS:
RUN IN 5 JTS 8 5/8 CASING, BREAK CIRCULATION
MIX 150 SK CEMENT, WASH UP + DISPLACE W/
12 1/2 BBL H₂O, SHUT IN @ 200 PSI, CEMENT
DID CIRCULATE

CHARGE TO: 701
 STREET _____
 CITY _____ STATE _____ ZIP _____

Global Oil Field Services, LLC
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____
 SIGNATURE Terry Austin

SERVICE
 DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____
 EXTRA FOOTAGE _____ @ _____
 MILEAGE _____ @ _____
 MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____
 PLUG & FLOAT EQUIPMENT
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

JOB LOG

SWIFT Services, Inc.

DATE 11-16-18 PAGE NO. 3

CUSTOMER T&E WELL NO. #4 LEASE Furthmyer JOB TYPE 2 stage TICKET NO. 27425

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	8:45							On location
								TD - 3510 Shoe - 35.92 Baffle @ 3474 Centralizers - 1,3,5,7,9,11,13,15,17,58 Baskets - 2#59 D.V. Tool - 59 @ 1000'
	9:30							Start Running Csg
	11:00							Circ on Bottom
	12:00	5.5	12					pump mud flush - 500 GAL
		5.5	20					pump KCL spacer
	12:15	5.5	35			300		pump cmt - 150 sks EA-2@15.5
	12:25							Drop plug - Wash p & L
	12:30	6.5	0					Start Disp
	12:45	5	84.75			800/1500		land plug - 144 psi - 800 # land psi - 1500 #
	12:50							Drop D.V. opening tool
	12:55	2.5	8			0		plug rat hole - 30 sks
	1:30					900		Open D.V. tool
		6	0			200		Start Cmt - 120 sks SMD @ 11.2 ppg
			65					Raise wgt to 14.5 ppg for 25 sks
			72					End cmt - Cmt circulating
	1:32	5	0			150		Start Disp
	1:35	5	24.5			500/1500		land plug - 144 psi - 500 land psi - 1500
								Release psi - 150
								*** Circulated 50 sks cmt top it
								JOB Complete
								Thanks David, Zach, & Kirby