



DEC 24 2018

PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1000335	1718	12/17/2018
INVOICE NUMBER			
92870340			

Pratt (620) 672-1201

B BEREKCO LLC  
 I 2020 N BRAMBLEWOOD  
 L L WICHITA  
 T KS US 67206  
 O ATTN: VICKEY LOVETTE

J LEASE NAME Six M Farms A 5-22  
 O LOCATION  
 B COUNTY Finney  
 S STATE KS  
 I JOB DESCRIPTION Cement-New Well Casing/Pi  
 T JOB CONTACT

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41150400	19919		Net - 30 days	01/16/2019
<i>For Service Dates: 12/14/2018 to 12/14/2018</i>				
0041150400				
171817246L Cement-New Well Casing/Pi 12/14/2018 CEMENT SURFACE CASING				
A-Serv Lite				
150 SK PREMIUM PLUS CEMENT	800.00 EA		7.41	5,928.00 T
2370 LBS Calcium Chloride	1.00 EA		1,393.65	1,393.65 T
238 LBS Celloflake	1.00 LB		1,418.45	1,418.45 T
Guide Shoe - Regular, 8 5/8" (Blue)	1.00 LB		501.94	501.94 T
Flapper Type Insert Float Valves. 8 5/8"	1.00 EA		380.00	380.00
Centralizer, 8 5/8" (Blue)	1.00 EA		280.00	280.00
Top Rubber Cement Plug, 8 5/8"	3.00 EA		90.00	270.00
240 Heavy Equipment Mileage	1.00 EA		225.00	225.00
Blending & Mixing Service Charge	1.00 MI		1,026.00	1,026.00
Proppant & Bulk Del. Chgs., per ton mil	1.00 SK		758.10	758.10
Depth Charge; 1001'-2000'	1.00 EA		3,597.77	3,597.77
Plug Container Utilization Charge	1.00 EA		855.00	855.00
60 PICKUP MILES	1.00 EA		142.50	142.50
"Service Supervisor, first 8 hrs on loc.	1.00 MI		153.90	153.90
Cement Data Acquisition Monitor	1.00 EA		99.75	99.75
	1.00 EA		313.50	313.50

PLEASE REMIT TO: SEND OTHER CORRESPONDENCE TO:  
 BASIC ENERGY SERVICES, LP BASIC ENERGY SERVICES, LP SUB TOTAL 17,343.56  
 PO BOX 841903 801 CHERRY ST, STE 2100 TAX 734.74  
 DALLAS, TX 75284-1903 FORT WORTH, TX 76102 INVOICE TOTAL 18,078.30





**PRESSURE PUMPING**

**Job Log**

Liberal Yard #1711 Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

Customer:	Berexco Inc		Cement Pump No.:	38117, 19919 6Hrs.	Operator TRK No.:	98816
Address:	2020 N BRAMBLEWOOD		Ticket #:	1718 17246 L	Bulk TRK No.:	14355, 37724 Jesse
City, State, Zip:	WICHITA KS 67206		Job Type:	Z42 - Cement Surface Casing		
Service District:	1718 - Liberal, Ks.		Well Type:	OIL		
Well Name and No.:	Six M Farms "A" 5-22		Well Location:	22,22,34	County:	Finney
					State:	Ks
<b>Type of Cmt</b>	<b>Sacks</b>	<b>Additives</b>	<b>Truck Loaded On</b>			
A-Serv Lite	800	3% Calcium Chloride, 1/4# Polyflake	14355, 37724	Jesse	Front	Back
Premium Plus Cement	150	2% Calcium Chloride, 1/4# Polyflake	19827, 19808	Albert	Front	Back
			14354, 19578	Ignacio	Front	Back
<b>Lead/Tail:</b>	<b>Weight #1 Gal.</b>	<b>Water Requirements</b>	<b>CU. FT.</b>	<b>Man Hours / Personnel</b>		
<b>Lead:</b>	12.3	11.52	1664	TT Man Hours:	60	
<b>Tail:</b>	14.8	6.33	201	# of Men on Job:	5	
Time (am/pm)	Volume (BBLs)	Pressure(PSI)	Description of Operation and Materials			
			ON LOCATION & SAFETY MEETING			
23:15			RIG TO CIRCULATE			
1:15			RIG TO PT			
2:35 AM			PRESSURE TEST TO 2080PSI			
2:40 AM			PUMP 800SX LEAD @ 12.3#			
2:45 AM	5	220	CEMENT RETURNS			
3:37 AM			PUMP 150SX TAIL @ 14.8#			
3:48	5.5	140	SHUTDOWN / DROP PLUG			
3:56			DISPLACE			
3:58 AM	5.1	90				
	5.1	90				
	5.1	120				
	5.1	150				
	5.1	210				
	5.1	290				
	5.1	320				
	5.1	390				
	5.1	470				
	5.1	520				
4:28	5.1	530	SLOW RATE TO 2.0BPM @ 470PSI			
	2	520				
4:36	2	520	LAND PLUG / PRESSURE UP TO 1020PSI			
4:38			RELEASE BACK --- FLOAT HELD			
			JOB COMPLETE			
Size Hole	12 1/4"	Depth	TYPE	Plug Container		
Size & Wt. Csg.	8 5/8" 23#	Depth	Packer	Depth		
ibg.	411.9psi	Depth	Retainer	Depth		
Top Plugs	42.16'	Type	Perfs	CIBP		
Customer Signature:	<i>Michael Johnson</i>		Basic Representative:	Daniel Beck		
			Basic Signature:	<i>Daniel Beck</i>		
			Date of Service:	12/14/2018		

Berexco LLC  
Six M Farms A5-22

