

JAN 14 2019



mf

PAGE	CUST NO	YARD #	INVOICE DATE
1 of 2	1000335	1718	01/10/2019
INVOICE NUMBER 92884778			

Pratt (620) 672-1201
 B BEREVCO LLC
 I 2020 N BRAMBLEWOOD
 L WICHITA
 L KS US 67206
 T
 O ATTN: VICKEY LOVETTE

J LEASE NAME Six M Farms A 5-22
 O LOCATION
 B COUNTY Finney
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41154333			Net - 30 days	02/09/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 01/08/2019 to 01/08/2019</i>				
0041154333				
171817204L Cement-New Well Casing/Pi 01/08/2019 Cement Production Casing				
A-Con' Blend	60.00	EA	11.16	669.60 T
AA2 Cement	185.00	EA	10.92	2,020.20 T
A-Con' Blend	250.00	EA	11.16	2,790.00 T
AA2 Cement	50.00	EA	10.92	546.00 T
Calcium Chloride	876.00	EA	0.63	551.88 T
Celloflake	78.00	EA	2.22	173.16 T
Gypsum	1,105.00	EA	0.45	497.25 T
C-17	111.00	LB	12.00	1,332.00 T
C-41P	56.00	EA	2.40	134.40 T
1172 Lbs. - Gilsonite	1.00	EA	468.80	468.80 T
Salt	1,302.00	EA	0.30	390.60 T
Two Stage Cement Collar, 5 1/2" (Red)	1.00	EA	6,100.00	6,100.00
5 1/2" Latch Down Plug & Assembly (Red)	1.00	EA	1,054.85	1,054.85
Auto Fill Float Shoe 5 1/2" (Blue)	1.00	EA	360.00	360.00
Turbolizer, 5 1/2" (Blue)	18.00	EA	110.00	1,980.00
5 1/2" Basket (Blue)	4.00	EA	290.00	1,160.00
Heavy Equipment Mileage	180.00	MI	4.50	810.00
Blending & Mixing Service Charge	545.00	BAG	0.84	457.80
Proppant & Bulk Del. Chgs., per ton mil	1,539.00	EA	1.50	2,308.50
Depth Charge; 4001'-5000'	1.00	EA	1,512.00	1,512.00
Additional Stage Charge	1.00	HR	1,296.00	1,296.00
Plug Container Utilization Charge	1.00	EA	150.00	150.00
"Unit Mileage Chg (PU, cars one way)"	60.00	MI	2.70	162.00
"Service Supervisor, first 8 hrs on loc.	1.00	EA	105.00	105.00



PAGE	CUST NO	YARD #	INVOICE DATE
2 of 2	1000335	1718	01/10/2019
INVOICE NUMBER			
92884778			

Pratt (620) 672-1201
 B BEREXCO LLC
 I 2020 N BRAMBLEWOOD
 L WICHITA
 L KS US 67206
 T
 O ATTN: VICKEY LOVETTE

J LEASE NAME Six M Farms A 5-22
 O LOCATION
 B COUNTY Finney
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.		TERMS	DUE DATE
41154333				Net - 30 days	02/09/2019
Cement Data Acquisition Monitor		QTY	U of M	UNIT PRICE	INVOICE AMOUNT
		1.00	EA	330.00	330.00

ACP *per bid*

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	27,360.04
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	761.12
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	28,121.16
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Berexco Inc	Cement Pump No.:	38117, 19919 16Hrs.	Operator TRK No.:	96816
Address:	2020 N BRAMBLEWOOD	Ticket #:	1718 17204 L	Bulk TRK No.:	30464, 19578 Willie 70897, 37725 Oscar
City, State, Zip:	WICHITA KS 67206	Job Type:	Z42 - Cement Production Casing		
Service District:	1718 - Liberal, Ks.	Well Type:	OIL		
Well Name and No.:	SIX M FARMS A 5-22	Well Location:	22,22,34	County:	Finney State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-Con' Blend	60	3% Calcium Chloride, 1/4# Celloflake	30464, 19578 Willie	Front	Back
AA2 Cement	185	10% Gypsum, 10% SALT, .5% C-17, 1/4# Defoamer	70897, 37725 Oscar	Front	Back
A-Con' Blend	250	3% CALCIUM CHLORIDE, 1/4# Celloflake	30463, 37547	Front	Back
Rat & Mouse	50		30463, 37547	Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	11.4	2.95	18.1	177	TT Man Hours:	89.5
Tail:	14.8	1.51	6.65	279.35		
Tail 2:	11.4	2.95	18.1	737.5		
					# of Men on Job:	4

Time (am/pm)	BPM	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
3:15							ON LOCATION & SAFETY MEETING
8:00							RUN FLOAT EQUIPMENT
11:30 AM							RIG TO CIRCULATE
12:30 PM							RIG TO P.T.
1:00 PM		13.4 slurry					PLUG RAT & MOUSE W/ 50SX @ 14.8#
13:34	7	31.5 slurry				150	PUMP LEAD 60SX @ 11.4# / STAGE 1
13:42	7	49.7 slurry				170	PUMP TAIL 185SX @ 14.8# / STAGE 1
1:50 PM							SHUTDOWN / DROP LATCH DOWN PLUG / WP
14:00	7	10				110	DISPLACE W/ 38.4BBL H2O
5:54	7	20				110	
	7	30				110	
	7	40				110	DISPLACE W/ 76.0BBL MUD
	8.3	50				180	
	8.3	60				150	
6:05	8.3	70				180	
	8	80				270	
	7.8	90				450	
	7.6	100				630	
	7.4	104				720	SLOW RATE TO 2.0BPM @ 440PSI
	2	110				550	LAND PLUG / PRESSURE UP TO 1660PSI

Size Hole	7 7/8"	Depth			TYPE	Plug Container	
Size & Wt. Csg.	5 1/2" 15.5#	Depth	4851.63'	DV Tool	3193.44'	Packer	Depth
Landing Press. 1	630.7psi	Landing Press. 2	508.3psi			Retainer	Depth
Top Plugs	42.50'	Type				Perfs	CIBP

Customer Signature:	Basic Representative:	Daniel Beck
	Basic Signature:	
	Date of Service:	1/8/2019



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Berexco Inc	Cement Pump No.:	38117, 19919 16Hrs.	Operator TRK No.:	96816
Address:		Ticket #:	1718 17204 L	Bulk TRK No.:	30464, 19578 Willie 70897, 37725 Oscar
City, State, Zip:		Job Type:	Z42 - Cement Production Casing		
Service District:	1718 - Liberal Ks	Well Type:	OIL		
Well Name and No.:	SIX M FARMS A 5-22	Well Location:	22,22,34	County:	Finney
				State:	Ks

Time (am/pm)	Volume (BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
14:24	2	114.4				700	LAND PLUG / PRESSURE UP TO 1660PSI
14:26							RELEASE BACK --- FLOAT HELD
2:30 PM							DROP OPENING TOOL
2:45 PM		1				850	PUMP OPENING TOOL @ 850PSI
2:53 PM							RIG TO CIRCULATE
18:50							RIG TO PT
19:00	7	131.3 slurry				640	PUMP 250SX @ 11.4# / STAGE 2
7:23 PM							SHUTDOWN / DROP CLOSING TOOL
19:31	7	10				250	
	7.2	20				350	
	7.2	30				470	
	7	40				530	
	7	50				600	
	7	60				670	
19:42	7	66				730	SLOW RATE TO 2.0BPM @ 590PSI
	2	70				600	
19:47	2	76				630	LAND CLOSING PLUG / PRESSURE UP TO 1480PSI
19:49							RELEASE BACK --- PLUG HELD
							JOB COMPLETE

Size Hole	7 7/8"	Depth				TYPE	Plug Container	
Size & Wt. Csg.	5 1/2" 15.5#	Depth	4851.63'	DV Tool	3193.44'	Packer	Depth	
Landing Press. 1	630.7psi	Landing Press. 2	508.3psi			Retainer	Depth	
Top Plugs	42.50'	Type				Perfs	CIBP	
						Basic Representative:	Daniel Beck	

Berexco LLC
Six M Farms #5-22

