



12258
12137

Fuzzzy
1-2-19

API # 15-035-24697-00-00

TICKET NUMBER 54360

LOCATION EL Dorado, KS

FOREMAN Fuzzzy

PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice #814814

KS

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
1-2-19	7496	Andes 27 #2	27	32	5	Cowley
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
SNR Kansas Operating			603	chance		
MAILING ADDRESS			713	Coj		
P.O. Box 18251			725	Fuzzzy		
CITY	STATE	ZIP CODE	577	Jacob		
OKC	OKLA	73154				

JOB TYPE Production HOLE SIZE 7 7/8 HOLE DEPTH 3464' CASING SIZE & WEIGHT 5 1/2 17#
 CASING DEPTH 3462 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.8 SLURRY VOL 69.4 WATER gal/sk _____ CEMENT LEFT in CASING 4'
 DISPLACEMENT 82.4 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting on w-w #14, Run float equip 11' shoe Jt with AFU
 float shoe + Latchdown Baffle. Turbolizers on 2-4-6-11-16-21-26-31
 Baskets 5-22-32 circulate 40 min. Pump 10 BBL water, mix 255 lbs cement
 in RH. mix 225 lbs class 'A' 490cc 290cc with 5# Kalsol and 1 1/2#
 phenosol per sk. Wash pump and lines. Drop plug and displace 803/4 BBL
 1000# lft press Land plug @ 1500#. float hold
 4' shoe Jt - 5 1/2

THANKS Fuzzzy crew

API # 15-035-24697-00-00

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0492	1	PUMP CHARGE	2300.00	2300.00
CE0002	50 miles	MILEAGE	7.14	357.00
CE0710	11.8 Ton	Ton mileage Delivery	8.72	1028.16
CC5800A	250 lbs	Class 'A'	20.00	5000.00
CC5325	470#	Calcium chloride	1.25	587.50
CC5965	940#	Bentonite	.30	282.00
CC6077	1250#	Kalsol	.50	625.00
CC6079	125#	Phenosol	1.35	168.75
CP8254	1	5 1/2 - Latchdown plug and Assy	400.00	400.00
CP8485	1	5 1/2 - AFU float shoe	585.00	585.00
CP8576	8	5 1/2 - Turbolizers	110.00	880.00
CP8651	3	5 1/2 - Reciprocating Baskets	360.00	1080.00
CE1130	4'	5 1/2 - shoe Jt	35.00	140.00
		subtotal		13433.00
		discount	35.90	4701.85
		subtotal		8732.04
		SALES TAX		408.95
		ESTIMATED TOTAL		9137.99

SCANNED

Flavin 3737

AUTHORIZATION Willie Mick TITLE Operations Manager DATE 1/2/19

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.