

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: _____
 Name: _____
 Address 1: _____
 Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Contact Person: _____
 Phone: (_____) _____
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - _____
 Spot Description: _____
 _____ - _____ - _____ - _____ Sec. _____ Twp. _____ S. R. _____ East West
 _____ Feet from North / South Line of Section
 _____ Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: _____
 Lease Name: _____ Well #: _____
 Date Well Completed: _____
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: _____
 Plugging Completed: _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: _____ Name: _____
 Address 1: _____ Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Phone: (_____) _____
 Name of Party Responsible for Plugging Fees: _____
 State of _____ County, _____, ss.
 _____ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically



ACE WELL SERVICE, INC.
 P. O. Box 209
 Russell, KS 67665
 (620)960-1818
 jjthomewood@gmail.com
 http://www.acewellservice.com

Invoice 3546R

DATE	PLEASE PAY	DUE DATE
03/08/2021	\$3,135.89	04/07/2021

BILL TO
 Fossil Creek Energy, LLC
 P.O. Box 915
 Russell, KS 67665

PLEASE DETACH TOP PORTION AND RETURN WITH YOUR PAYMENT.

LEASE **RIG #**
 Driscoll #1 Rig #3

DATE	DESCRIPTION	QTY	RATE	AMOUNT
02/26/2021	Double Drum Rate Per Hour 5:45 MIRU, got equipment ready to pull well, clean tools and location, shut down, 7:15. W-1.50	1.50	165.00	247.50T
03/01/2021	Double Drum Rate Per Hour Scheck's dug pit, 7:00 - got trailer, went to grab boards to make floor over cellar from digging out braiding head, latched onto polish rod, pulled tight, worked pump and got to unseat, laid rods out on trailer, pulled 1 1/4 x 16' with 6' liner, 6' 8' - 3/4, 123 - 3/4 and 2 x 1 1/2 x 10', top 30 - 3/4 rods were good, then rods had hard scale build up, switch over for tubing, laid tubing out on a trailer, tubing wouldn't lay out, had to walk every joint out, tubing had hard scale build up, had to clean scale out of tongs and spiders about every 10-15 jts, pulled 100 - 2 3/8, SN and 3' perf sub, broke off head, had 10rd casing, needed change over nipple, call and found change over, hook up Gemini, perf 925' and 1400', put on work head, tally and ran 90 - jts to 2850', hook up cement, pump 13sx gel, 75sx cement and 100 lbs hulls, unhook, pull 44 - jts to 1450', hook up cement, pump 125sx cement and 200 lbs hulls, unhook, pull 21 - jts, top off casing with 20sx cement, clean tools and location, shut down, 7:30. W-12.50	12.50	165.00	2,062.50T
03/02/2021	Double Drum Rate Per Hour 7:00 - pick up floors, clean tools and location, RDMO, 8:45. W-1.75	1.75	165.00	288.75T
	Solvent Used for Cleanup -- Per Gal	15	3.00	45.00
	Thread Dope Per Trip	1	25.00	25.00T
	Circulating Head (Less Rubber) Per Job	1	50.00	50.00T
	2-Inch or 2 1/2-Inch Circulating Head Rubbers	1	125.00	125.00T
	7" 8rd to 10rd Nipple	1	50.00	50.00T

Go paperless! Receive invoices and notifications via email! To enroll, call us at (620) 960-1818 or email us at jjthomewood@gmail.com and provide us with your contact information.

SUBTOTAL	2,893.75
TAX	242.14
TOTAL	3,135.89

TOTAL DUE \$3,135.89

Accounts not paid within 30 days of the date of the invoice are subject to a 2% monthly finance charge.



WELL SERVICE, INC.

Company: First Creek Energy Date: 2/26/2021
Lease: Dressell #1 Well No.: _____ Co.: Russell KANSAS
Job Description: plug well
Cause of Failure: _____

WELL RECORD

PULLED FROM WELL				RERAN IN WELL			
Feet	Joints	Description	Condition	Equipment	Feet	Joints	Description
16	1	1 1/2"		Polish Rod			
6	1	1 1/2"		Liner			
	2	6.5' 3/4"		Rod Subs			
	123	3/4"		Rods			
				Rods			
				Rods			
				Rods			
	1	2x10x10		Pump			
				Tubing Subs			
	100	2 3/8"		Tubing			
				Tubing			
	1	2 3/8"		Bbl. Seat N.			
		where set. Type: Size:		Packer or Tubing Achor			where set. Type: Size:
3	1	2 3/8" perf sec		Mud Anchor			

- Paint _____
- Solvent 15 Gal x \$3.00 = \$45.00
- Thread Dope 1/2 lb # \$25.00 each = \$25.00
- Stuff Box Rub _____
- Fishing Tool _____
- Circ Head 7" _____
- Circ Rubber New 2 3/8" Used _____
- Packer (type) _____
- Plug _____
- Sand Pump _____
- Swab Equip _____
- Oil Saver Rub _____
- Swab Cups _____

Unit No. 3
Operator Jean
Floorman Mike
Floorman Wayne

Hrs.	Per Hrs.	Amount
15.75	165	2578 75
EXTRA EQUIP		295 00
SALES TAX		242 14
TOTAL		\$ 3,135 89

Bad	Replacements
# _____ jts _____	# _____ jts _____
# _____ rods _____	# _____ rods _____
Rod Boxes Replaced 3/4" _____	7/8" _____ 1" _____

Testing tbg
Who tested: _____
Results: _____
Items used from ACE: 7" Sid to load nipple \$50.00
Items used from other suppliers: _____



QUALITY OILWELL CEMENTING, INC.
 PO Box 32 - 740 West Wichita Ave, Russell KS 67665
 Phone: 785-324-1041 fax: 785-483-1087
 Email: cementing@ruraltel.net

Date: 3/1/2021
 Invoice # 2098

P.O.#:
 Due Date: 3/31/2021
 Division: *Russell*

Invoice

Contact:

Address/Job Location:

Fossil Creek

Reference:

JERRY DRISCOL 1 SEC 27-14-14

Description of Work:

PLUG JOB

Services / Items Included:	Quantity	Price	Taxable	Item	Quantity	Price	Taxable
Labor		\$ 298.26	Yes				
Common-Class A	205	\$ 2,823.52	Yes				
POZ Mix-Standard	135	\$ 631.83	Yes				
Premium Gel (Bentonite)	25	\$ 484.74	Yes				
Bulk Truck Matl-Material Service Charge	450	\$ 300.87	Yes				
Cottonseed Hulls	6	\$ 135.19	Yes				
Bulk Truck Mileage-Job to Nearest Bulk Plant	15	\$ 35.10	Yes				

Invoice Terms:

Net 30

SubTotal: \$ 4,709.52

Discount Available ONLY if Invoice is Paid & Received within listed terms of invoice: \$ (117.74)

SubTotal for Taxable Items: \$ 4,591.78

SubTotal for Non-Taxable Items: \$ -

Total: \$ 4,591.78

Tax: \$ 390.30

8.50% Russell County Sales Tax

Amount Due: \$ 4,982.08

Applied Payments:

Balance Due: \$ 4,982.08

Thank You For Your Business!

Past Due Invoices are subject to a service charge (annual rate of 24%)

This does not include any applicable taxes unless it is listed.

©2008-2013 Straker Investments, LLC. All rights reserved.

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-1071
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 2098

Date	3/1/2021	Sec.	27	Twp.	14	Range	14	County	Russell	State	Kansas	On Location		Finish	6:15pm
								Location Russell 35 35 E 1/2 S E into							
Lease Terry Driscoll				Well No. 1				Owner				To Quality Oilwell Cementing, Inc.			
Contractor Ace Well Serv								You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Type Job plug								Charge To Fossil Creek							
Hole Size				T.D.				Street							
Csg. 7"				Depth				City				State			
Tbg. Size 2 3/4				Depth 2850'				The above was done to satisfaction and supervision of owner agent or contractor.							
Tool				Depth				Cement Amount Ordered 450 60 40 4 gel							
Cement Left in Csg.				Shoe Joint				600# hulls 13 gel							
Meas Line				Displace				Common 205							
EQUIPMENT															
Pumptrk 18		No.	Cementer		Helper		Tim		Poz. Mix 135						
Bulktrk 13		No.	Driver		Doug		Tom		Gel. 25						
Bulktrk pu		No.	Driver		David				Calcium						
JOB SERVICES & REMARKS															
Remarks:				Hulls 300# (6)				Salt							
Rat Hole used 340 sks				Flowseal											
Mouse Hole 13 gel 300# Hulls				Kol-Seal											
Centralizers				Mud CLR 48											
Baskets				CFL-117 or CD110 CAF 38											
D/V or Port Collar				Sand											
				Handling 450											
2850' mixed 13 gel with 25 sks with 100# Hulls				Mileage								FLOAT EQUIPMENT			
1450' mixed 12.5 sks with 200# hulls				Guide Shoe											
680' Mixed 120 sks to circulate to surface				Centralizer											
pulled Tubing and topped off with 20 sks				Baskets											
				AFU Inserts											
				Float Shoe											
				Latch Down											
				Pumptrk Charge plug											
Cement Did Circulate				Mileage 15 Jimmy											
X Signature <i>JA</i>												Tax			
												Discount			
												Total Charge			

Thanks



1023 Reservation Rd
Hays, KS 67601-3982

Office: 785-625-1182 or 785-625-1118
Fax: 785-625-1180

INVOICE
5612

Fossil Creek Energy LLC
PO BOX 915
RUSSELL KS 67665-0915

Invoice Date 03/02/21
11025 Lease Jerry Driscoll
Well 1
County Russell
State KS

Service Date	Job Ticket	DESCRIPTION	
gavin@fcenergy.org		joel@fcenergy.org	derek@fcenergy.org
03/01/21	3225	Perforate	\$ 1,150.00

SubTotal \$ 1,150.00
Tax \$ -

Please Pay From This Invoice

TOTAL DUE \$ 1,150.00

We Appreciate Your Business !

Terms: Invoice payable net 30 from date on invoice.

Past due invoices subject to finance charge at maximym rate allowed by state law.

