



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	Merit Energy	Cement Pump No.:	38117, 19919 9Hrs.	Operator TRK No.:	96816
Address:	gardencity.invoices@meritenergy.com	Ticket #:	1718 17280 L	Bulk TRK No.:	19827, 19808 Oscar
City, State, Zip:	AFE# 62983	Job Type:	Z42 - Cement Conductor Casing		
Service District:	1718 - Liberal, Ks.,	Well Type:	OIL		
Well Name and No.:	River Bend #8	Well Location:	34,24,32	County:	Finney State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
Premium Plus Cement	190	3% Calcium Chloride, 1/2# Celloflake	19827, 19808 Oscar	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Tail:	14.8	1.36	6.34	258.4	TT Man Hours:	39.5
					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing		
12:15							ON LOCATION
12:20							SAFETY MEETING
12:30 PM							RIG UP
6:45 AM							RIG TO P.T.
6:48 AM							PRESSURE TEST TO 1200PSI
6:51 AM	5	46.0 slurry			150		PUMP TAIL 180SX @ 14.8#
7:05	4.9	10			120		DISPLACE
							11BBLs IN, CEMENT RETURNS
7:09 AM	4.8	14.2			110		SHUTDOWN / CLOSE IN
							JOB COMPLETE

Circ 3 BBLs to the P.T.

Size Hole	17 1/2"	Depth	113'		TYPE	Swage	
Size & Wt. Csg.	13 3/8" 48#	Depth	111'	New / Used	Packer	Depth	
Landing Press.	33.9psi	Depth			Retainer	Depth	
Shoe Jt.	20'	Type			Perfs	CIBP	

Customer Signature: <i>X</i>	Basic Representative:	Daniel Beck
	Basic Signature:	<i>Daniel Beck</i>
	Date of Service:	2/20/2019

River Bend #8

