

mf

APR 30 2019



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1000335	1718	04/23/2019
INVOICE NUMBER 92956217			

Pratt (620) 672-1201
 B BEREEXO LLC
 I 2020 N BRAMBLEWOOD
 L WICHITA
 T KS US 67206
 O ATTN: VICKEY LOVETTE

J LEASE NAME *Charley* 1-21
 O LOCATION
 B COUNTY Finney
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41171854			Net - 30 days	05/23/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 04/22/2019 to 04/22/2019</i>				
0041171854				
171819397L Cement-New Well Casing/Pi 04/22/2019 Production				
A-Serv Lite	770.00	SK	7.41	5,705.70 T
150 Sk - AA2 Cement	1.00	SK	1,555.50	1,555.50 T
846 Lb. - Gypsum	1.00	LB	363.78	363.78 T
831 Lb. - Salt	1.00	LB	240.99	240.99 T
751 Lb. - Gilsonite	1.00	LB	285.38	285.38 T
C-17	71.00	LB	11.40	809.40 T
C-41P	36.00	LB	2.28	82.08 T
134 Lb. - Celloflake	1.00	LB	282.74	282.74 T
4 1/2" Float Shoe(Blue)	1.00	EA	340.00	340.00
4 1/2" Latch Down Plug & Assembly (Red)	1.00	EA	720.00	720.00
Two Stage Cement Collar, 4 1/2" (Red)	1.00	EA	4,500.00	4,500.00
4 1/2" Basket (Blue)	3.00	EA	270.00	810.00
Turbolizer, 4 1/2" (Blue)	13.00	EA	85.00	1,105.00
240 Miles - Heavy Equipment Mileage	1.00	MI	1,027.20	1,027.20
920 Sk-Blending & Mixing Service Charge	1.00	SK	736.00	736.00
2594 Tn/Mi-Proppant & Bulk Del. Chgs	1.00	EA	3,709.42	3,709.42
Depth Charge, 4001'-5000'	1.00	HR	1,436.40	1,436.40
Additional Stage Charge	1.00	HR	1,231.20	1,231.20
Plug Container Utilization Charge	1.00	EA	142.50	142.50
60 Miles - Light Vehicle Mileage	1.00	MI	154.20	154.20
Cement Data Acquisition Monitor	1.00	EA	313.50	313.50
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	3.00	EA	35.00	105.00

ACP per bid

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	25,730.99
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	741.38
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	26,472.37
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	BEREXCO LLC.	Cement Pump No.:	38119-19570 <i>17 hrs</i>	Operator TRK No.:	96815
Address:		Ticket #:	1718-19397 L	Bulk TRK No.:	30463-19578 14355-37724
City, State, Zip:		Job Type:	Z42-PRODUCTION		
Service District:		Well Type:	OIL		
Well Name and No.:	CHARLEY 1-21	Well Location:	21-23-31	County:	FINNEY State: KS

Type of Cmt	Sacks	Additives	Truck Loaded On		
AA2	150	10%GYPSUM, 10%SALT, 5#GILSONITE, .5%FL, .25#DEFOAMER	30463-19578	Front	Back
A SERV LITE	770	6%GEL, 1/4#POLYFLAKE	14355-37724	Front	Back
			14354-19808	Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	14.8	1.51	6.65	226.5	Man Hours:	<i>584</i>
Tail:	12.7	1.89	10.29	1455.3	# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
22:00							ON LOC, SAFTEY MTG, R.U.
9:38						3500	TEST LINES
9:41 AM	6.7					280	START LEAD @ 12.6#
9:57 AM	7	79				160	ON TAIL @ 14.8#
10:03 AM		27					SHUT DOWN, DROP PLUG, WASHUP
10:10	7					130	START DISPLACEMENT
10:15	7	30				380	ON MUD DISPLACEMENT
10:22 AM	2.5	70				570	SLOW RATE
10:26		80.25				690-1300	PLUG DOWN
10:28							RELEASE PSI
10:30							DROP BOMB
10:50	4	18				800-180	OPEN TOOL
11:00							CIRC W/ RIG 4 HRS
15:00							PLUG RAT & MOUSE
15:13	6.5					170	START LEAD @ 12.6#
15:47	4	163				120	ON TAIL @ 14.8#
15:53		13.5					SHUT DOWN, DROP PLUG, WASHUP
15:57	7					20	START DISPLACEMENT
16:03	3	35				430	SLOW RATE
16:10		51				780-1500	PLUG DOWN, CLOSED TOOL
16:12							RELEASED PSI
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	7 7/8	Depth	5050' RTD 5045LTD		TYPE			
Size & Wt. Csg.	4 1/2 10.5	Depth	5048.25	New / Used	D.V.TOOL	YES	Depth	3194.45
tbq.		Depth			Retainer		Depth	
Top Plugs		Type			Perfs		CIBP	

Customer Signature: <i>[Signature]</i>	Basic Representative:	CHAD HINZ
	Basic Signature:	<i>[Signature]</i>
	Date of Service:	4/22/2019

BEREXCO
CHARLEY 1-21

