



BASICSM
ENERGY SERVICES

PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1003965	1718	06/14/2019
INVOICE NUMBER			
92990515			

Pratt (620) 672-1201
 B STELBAR OIL CORPORATION INC
 I 1625 N WATERFRONT PKWY STE 200
 L WICHITA
 L KS US 67206
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME OKESON 1-36
 O LOCATION
 B COUNTY WALLACE
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41179235	19572		Net - 30 days	07/14/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 06/13/2019 to 06/13/2019</i>				
0041179235				
171819484L Cement-New Well Casing/Pi 06/13/2019 CEMENT SURFACE CASING				
60/40 Poz	375.00	SK	6.60	2,475.00 T
94 LBS Celloflake	1.00	LB	191.76	191.76 T
969 LBS Calcium Chloride	1.00	LB	562.02	562.02 T
Wooden Cement Plug, 8 5/8"	1.00	EA	88.00	88.00
Baffle Plate Aluminum, 8 5/8" (Blue)	1.00	EA	93.50	93.50
Centralizer, 8 5/8" (Blue)	3.00	EA	49.50	148.50
100 Light Vehicle Mileage	1.00	MI	248.00	248.00
200 Heavy Equipment Mileage	1.00	MI	826.00	826.00
Proppant and Bulk Delivery Charges	1.00	MI	2,228.70	2,228.70
Depth Charge, 0'-1000'	1.00	HR	550.00	550.00
Blending & Mixing Service Charge	375.00	SK	0.77	288.75
Plug Container Utilization Charge	1.00	EA	137.50	137.50
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	2.00	EA	35.00	70.00

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	7,982.73
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	242.16
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	8,224.89
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Stelbar Oil Corporation	Cement Pump No.:	19752 3Hrs 19572	Operator TRK No.:	78938 Angel
Address:		Ticket #:	1718 19484 L	Bulk TRK No.:	19827 Victor
City, State, Zip:		Job Type:	Z42 - Cement Surface Casing		
Service District:	1718 - Liberal Ks.	Well Type:	OIL		
Well Name and No.:	Okeson #1-36	Well Location:	36,15,42	County:	Wallace State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
60/40 POZ	375	3% CC, .25 PPS CelloFlake	19827 Victor	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	14.8	1.21	5.18	453.75	Man Hours:	45
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
0:15							On Location
0:30							Safety Meeting
12:50 AM							Rig Up
4:30 AM							Pressure Test To 1500psi
4:39 AM	6	5				200	Pump 5 bbl H2O Spacer
4:41	6	80.8				150	Pump Cement @ 14.8#
5:00							Shut Down - Drop Plug
5:03 AM	6	25.5				260	Displacement
5:15							Landed Plug Pressure Up To 500psi
5:20							Release Back --- Float Held
							*** Cement To Surface ***
							Job Completed
							Thank You

Size Hole	12 1/4"	Depth			TYPE	Plug Container	
Csg.	8 5/8" 23#	Depth	442.12'	New / Used	Packer	Depth	
Shoe jt.	40.3'	Depth			Retainer	Depth	
Landing Psi	128.8psi	Type			Perfs	C/BP	

Customer Signature:	Basic Representative:	Angel Echevarria
	Basic Signature:	
	Date of Service:	6/13/2019