



P. O. Box 466
Ness City, KS 67560
Off: 785-798-2300



Invoice

DATE	INVOICE #
6/7/2019	32309

BILL TO
Palomino Petroleum Inc. 4924 S E 84th Street Newton, KS 67114-8827

RECEIVED
 JUN 13 2019

- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#1	Marilyn	Ness	Express	Oil	Development	Acid & Squeeze	Gideon

PRICE REF.	DESCRIPTION	QTY	UM	UNIT PRICE	AMOUNT
575D	Mileage - 1 Way	15	Miles	5.00	75.00
578D-D	Pump Charge - Deep Squeeze (> 1500 Ft.)	1	Job	1,400.00	1,400.00
300 - 15%	Regular Acid	250	Gallons	2.00	500.00
230	Surf-3 ESA-N35 (Losurf 300)	1	Gallon(s)	25.00	25.00
235	INH.1 ESA-28	1	Gallon(s)	40.00	40.00
325	Standard Cement	75	Sacks	13.50	1,012.50T
581D	Service Charge Cement	75	Sacks	1.85	138.75
582D	Minimum Drayage Charge	1	Each	250.00	250.00
	Subtotal				3,441.25
	Sales Tax Ness County			6.50%	65.81

We Appreciate Your Business!	Total \$3,507.06
-------------------------------------	-------------------------



TICKET 032309

CHARGE TO: Plomino Petroleum
 ADDRESS
 CITY, STATE, ZIP CODE

PAGE 1 OF 1

SERVICE LOCATIONS

1. Ness City, KS WELL/PROJECT NO. # 1 LEASE Marlyn COUNTY/PARISH Ness STATE KS CITY Land DATE 6-7-2019 OWNER

2. TICKET TYPE SERVICE SALES CONTRACTOR Express RIG NAME/NO. SHIPPED VIA air DELIVERED TO Location ORDER NO.

3. WELL TYPE Oil WELL CATEGORY Development JOB PURPOSE Acid + Squeeze WELL PERMIT NO.

4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/PART NUMBER	ACCOUNTING		DESCRIPTION	QTY.	U/M	QTY.	U/M	UNIT PRICE	AMOUNT
		LOC	ACCT DF							
576		1		MILEAGE <u>Trk #112</u>	15	mi	1	job	1400.00	1400.00
578		1		<u>Pump Change</u>						
300		1		<u>Regular Acid</u>	15	gal	250	gal	2.00	500.00
230		1		<u>Surf-3</u>	1	gal	1	gal	25.00	25.00
235		1		<u>Inhib-1</u>	1	gal	1	gal	40.00	40.00
325		1		<u>Standard CMT</u>	75	skts	13	skts	1.00	1012.50
581		1		<u>CMT Service Charge</u>	75	skts	1	skts	1.85	138.75
582		1		<u>Minimum Drillage Charge</u>	250	skts	1	skts	2.00	200.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS.

DATE SIGNED 6-7-2019 TIME SIGNED 10:16 A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UNDECIDED	DISAGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				1
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TOTAL
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				3507.00

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR Adam Fuchs APPROVAL Adam Fuchs

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 6-7-2019 PAGE NO. 1 of 2

CUSTOMER Palomino Petroleum WELL NO. #1 LEASE Marilyn B JOB TYPE Acid + Squeeze TICKET NO. 082309

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0830							On Location 2 7/8" 5 1/2' Perfs: 4466'-67' PKR: 4356 4456'-67' Spot: 4468
	0845 0850	3 1/2	25	✓		350		Load Hole Set PKR
	0855	1/2	1/2	✓		3000		Pressure Test to 3000 PSI * Hold Release Pressure
	0905 0920	3 1/2 1/2	26 1/3 0	✓ ✓		1200		Spot Acid 6-Acid 20 1/3-H2O Stage @ 1200 PSI -> Brake
		2	3	✓		250		Treat
	0925 0930							Pull up + Set PKR Injection Rate
		4	14	✓		850		
	0940							Swab back 40 bbls
	1030 1035						500	Pressure Test BS to 500 * Hold * Load Tubing - Take Injection Rate
		3 3	16 4	✓ ✓		0 500		IJ
	1045	3 1/2	16	✓				Mix 75 sks Standard CMT @ 15.5 ppm
	1055							Wash out Pump + Lines
	1100	3 1/2	0	✓		0		Start Displacement
		3 1/2	16	✓		1,000		
		3	17	✓		1700		
		2 1/2	18	✓		2300		
		1	19	✓		2400		
		1/2	19 3/4	✓		2500		Squeezed off
	1110							Wash up Trkr #118

JOB LOG

SWIFT Services, Inc.

DATE 6-7-2019 PAGE NO. 2 of 2

CUSTOMER Palomino Petroleum WELL NO. #1 LEASE Marilyn JOB TYPE Acid + Squeeze TICKET NO. C932309

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
								Cont. ...
	1120	1/2	0		✓		750	Pressure up BS to 750 BS
		1/2	0	✓		1800		Pressure Test Squeeze *Hold* Release Pressure -Unset PKR-
	1130	2	25		✓		600	Wash down 3 Joints of tubing
	1150	3	35		✓		450	Reverse Clean
	1200							Set PKR
		1/2	0		✓		500	Pressure BS to 500
		1/2	0	✓		1800		Pressure Squeeze to 1800 *Hold*
								Release Tb + BS Pressure
	1215							Job Complete
								75 sks of Standard CMT used *40 sks in Perfs*
								Thank You
								Gideon, Preston, Kirby, + Wayne