

**ATTACHMENT TO ACO-1**

**WELL NAME:** Evelyn Schlegel 2 – API #15-135-26071-0000

**LOC:** NW SE

Sec. 10-19S-25W

Ness County, KS

	<b>SAMPLE TOPS</b>	<b>LOG TOPS</b>
Anhydrite	1748 (+716)	1747 (+715)
Anhydrite Base	1788 (+676)	1787 (+675)
Heebner	3832' (-1368')	3836 (-1372)
Lansing	3874' (-1410')	3878 (-1414)
Base KC	4193' (-1729')	4197 (-1733)
Marmaton	4214' (-1750')	4214 (-1750)
Fort Scott	4384' (-1920')	4386 (-1922)
Cherokee	4410' (-1946')	4411 (-1947)
Mississippi Dolo Por	4489' (-2025')	4493 (-2029)
RTD	4495' (-2031')	4498 (-2034)

**DST #1**                    **4427-4495'**                    **Zone: Mississippi Dolomite**

Times:                    30-45-45-60

1<sup>st</sup> open:                1/4" built to 8".

2<sup>nd</sup> open:                WSB built to 11 1/2".

Recovery:              200' GIP

                              108' Oil

                              30' GCO (20% G, 80% O)

                              30' SLGCHMCO (5% G, 65% O, 30% M)

                              63' SLMCO (95% O, 5% M)

                              63' SLOCSLGCM (15% G, 5% O, 80% M)

                              Total Fluid 294' – Tool Sample: 51% gas, 43% oil, 6% mud

IHP:    2132                    FHP:    2123

IFP:    20-72                    FFP:    80-126

ISIP:    1292                    FSIP:    1267                    TEMP: 126°

