

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4455**
 Foreman David Gardner
 Camp Eureka

API# 15-077-22181

| Date | Cust. ID # | Lease & Well Number | Section | Township | Range | County | State | |
|---------------------|--------------------------------------|---------------------|---------|----------|--------|--------|--------|--------|
| 5-14-19 | 1320 | Sanders #3 | 4 | 31 S | 7W | Harper | KS | |
| Customer | Mailing Address | City | State | Zip Code | Unit # | Driver | Unit # | Driver |
| Hartman Oil Co. INC | 10500 E. Berkeley Sq. PKWY, Ste. 100 | Wichita | KS | 67206 | 105 | Jason | | |
| | | | | | 110 | Josh | | |

Job Type Surface Hole Depth 263' Slurry Vol. 48 Bbl Tubing _____
 Casing Depth 256.13' Hole Size 12 1/4 Slurry Wt. 15# Drill Pipe _____
 Casing Size & Wt. 23# 8 5/8" Cement Left in Casing 10' +/- Water Gal/SK 6.5 Other _____
 Displacement 116.5 Bbl Displacement PSI _____ Bump Plug to _____ BPM 5

Remarks: Safety Meeting. Rig up to 8 5/8" casing. Break circulation w/ 10 Bbl fresh water. Mixed 200 sks Class 'A' cement w/ 3% Cactz, 2% Gel, 1/4" Floseal/sk @ 15#/gal, yield: 1.35 = 48 Bbl Slurry. Displace w/ 116.5 Bbl fresh water. Shut down. Close casing in. Set cellar out and had good cement to surface. Job complete. Rig down.

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|--|--------------|------------------------------------|----------------|----------|
| C101 | 1 | Pump Charge | 890.00 | 890.00 |
| C107 | 100 | Mileage | 4.20 | 420.00 |
| C200 | 200 SKS | Class 'A' Cement | 15.75 | 3150.00 |
| C205 | 560 # | Cactz @ 3% | .63 | 352.80 |
| C206 | 375 # | Gel @ 2% | .21 | 78.75 |
| C209 | 50 | Floseal @ 1/4"/sk | 2.35 | 117.50 |
| C108B | 9.4 Tons | Ton Mileage - Bulk Truck | 1.40 | 1316.00 |
| <u>Thank You</u> | | | | |
| | | | Sub Total | 6,325.05 |
| | | | Less 5% | 328.27 |
| | | | Sales Tax 6.5% | 240.44 |
| Authorization <u>[Signature]</u> 5/14/19 Title _____ | | | Total | 6,237.22 |

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.