

QUALITY WELL SERVICE, INC.

Inv. 7110
C-2013

Federal Tax I.D. # 481187368

Home Office 30060 N. Hwy 281, Pratt, KS 67124

Mailing Address P.O. Box 468

Office 620-727-3410
Fax 620-672-3663

Rich's Cell 620-727-3409
Brady's Cell 620-727-6964

| Date | Sec. | Twp. | Range | County | State | On Location | Finish |
|--|---------------|------|--|---|-------|-------------|--------|
| 4-27-19 | 28 | 29S | 15W | PRATT | KS | | |
| Lease Addie | Well No. 4 | | Location PRATT, KS W on Hwy 54 to 140 th Rd | | | | |
| Contractor WW Dzlg Rig #14 | | | | Owner 10S to 100 th Rd 1E to 130 th 7S E. into | | | |
| Type Job Surface | | | | To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed. | | | |
| Hole Size 12 1/4 | T.D. 267' | | | | | | |
| Csg. 8 5/8 23 # | Depth 267' | | Charge To Griffin | | | | |
| Tbg. Size | Depth | | Street | | | | |
| Tool | Depth | | City | | State | | |
| Cement Left in Csg. 25 | Shoe Joint 25 | | The above was done to satisfaction and supervision of owner agent or contractor. | | | | |
| Meas Line | Displace 15.5 | | Cement Amount Ordered 300 sk Common | | | | |
| EQUIPMENT | | | | 2 1/2 GAL 3 1/2 CL 1/2" PS USEO 275 sk | | | |
| Pumptrk 8 No. | TI | | Common 275 sk | | | | |
| Bulktrk 10 No. | SALCE | | Poz. Mix | | | | |
| Bulktrk No. | | | Gel. 5 sk | | | | |
| Pickup No. | | | Calcium 10 sk | | | | |
| JOB SERVICES & REMARKS | | | | Hulls | | | |
| Rat Hole | | | Salt | | | | |
| Mouse Hole | | | Flowseal 137.5 lbs | | | | |
| Centralizers | | | Kol-Seal | | | | |
| Baskets | | | Mud CLR 48 | | | | |
| D/V or Port Collar | | | CFL-117 or CD110 CAF 38 | | | | |
| Run 6 #1's 8 5/8 23 # Csg set @ 267' | | | | Sand | | | |
| Csg on Bottom Hookup to Csg | | | | Handling 290 | | | |
| Break Circ w leg | | | | Mileage 25 | | | |
| START Pumping 5 Bbls H ₂ O | | | | 8 5/8 FLOAT EQUIPMENT | | | |
| START mix Pump 275 sk | | | | Guide Shoe HEAD & manifold | | | |
| Common 2 1/2 GAL 3 1/2 CL 1/2" PS @ 14.8 1/4 | | | | Centralizer 8 5/8 WOODEN Plug | | | |
| SHUT DOWN | | | | Baskets | | | |
| RELEASE 8 5/8 WOODEN Plug | | | | AFU Inserts | | | |
| START DISP | | | | Float Shoe | | | |
| Plug down 15.5 Bbls | | | | Latch Down | | | |
| Close Valve on Csg | | | | SERVICE Sup. | | | |
| Good circ thru JOB | | | | LMV 25 | | | |
| CIRC CNT TO PT | | | | Pumptrk Charge 5CF | | | |
| Thank you | | | | Mileage 50 | | | |
| PLEASE Call AGAIN | | | | Tax | | | |
| TODD TI TAKE | | | | Discount | | | |
| John [Signature] | | | | Total Charge | | | |

X Signature