

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

TEMPORARY ABANDONMENT WELL APPLICATION

OPERATOR: License#
Name:
Address 1:
Address 2:
City: State: Zip:
Contact Person:
Phone:
Contact Person Email:
Field Contact Person:
Field Contact Person Phone:

API No. 15-
Spot Description:
Sec. Twp. S. R.
GPS Location: Lat: Long:
Datum: NAD27 NAD83 WGS84
County: Elevation:
Lease Name: Well #:
Well Type: Oil Gas OG WSW Other:
SWD Permit #: ENHR Permit #:
Gas Storage Permit #:
Spud Date: Date Shut-In:

Table with 7 columns: Conductor, Surface, Production, Intermediate, Liner, Tubing. Rows include Size, Setting Depth, Amount of Cement, Top of Cement, Bottom of Cement.

Casing Fluid Level from Surface: How Determined? Date:
Casing Squeeze(s): to w / sacks of cement, to w / sacks of cement. Date:
Do you have a valid Oil & Gas Lease? Yes No
Depth and Type: Junk in Hole at Tools in Hole at Casing Leaks: Yes No Depth of casing leak(s):
Type Completion: ALT. I ALT. II Depth of: DV Tool: w / sacks of cement Port Collar: w / sack of cement
Packer Type: Size: Inch Set at: Feet
Total Depth: Plug Back Depth: Plug Back Method:

Geological Data:

Table with 4 columns: Formation Name, Formation Top, Formation Base, Completion Information. Rows 1 and 2.

UNDER PENALTY OF PERJURY I HEREBY ATTEST THAT THE INFORMATION CONTAINED HEREIN IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE

Submitted Electronically

Do NOT Write in This Space - KCC USE ONLY
Date Tested: Results: Date Plugged: Date Repaired: Date Put Back in Service:
Review Completed by: Comments:
TA Approved: Yes Denied Date:

Mail to the Appropriate KCC Conservation Office:

Table with 2 columns: Office Address, Phone. Rows for District Office #1, #2, #3, #4.

Operating Report

Well	Brocher A 1-2			STR	2-21S-15W	Cty	Pawnee	State	Kansas
Well Type	Gas	Well Status	TA-S2	Location	E2 E2 SE (1243 FSL 333 FEL)				
PBTD:	3,860	TD:	3,900	Pumper	Not Assigned				
Equip:				Surf Csg	8.625" OD, 23# @ 878' w/ 210 sx. 210sx A-Con, 3%cc				
				Inter Csg					
				Prod Csg	5.5" OD, 14# @ 3885' w/ 160 sx. Cement casing with 135sx AA-2, 25sx 60/40 Pozmix. Scavenger Cmt. top @ 3000 by CBL.				
				Perfs	Winfield 1862-66 3633-44 3361-66				
PR				Tbg Subs					
Ponies				2 3/8 Tbg. Jts	2 1/16 Tbg. Jts				
1" Rods #	1" FG Rods #			2 7/8 Tbg. Jts	3 1/2 Tbg. Jts				
7/8" Rods #	7/8" FG Rods #			Tbg Pump					
3/4" Rods #	3/4" FG Rods #			Oth Tbg					
5/8" Rods #				Packer					
Sinker Bars	SB Size			Mud Anchor					
Oth Rods				DH Comments					
Pump									

Date and Service Type

6/10/2020 Activity Type - MIT

M.I.R.U. H-D Well Service double drum pole pulled 16 ft polish rod w/ 7' liner singled down 75 3/4 rods.

Pulled 2-3/8 x 1-1/4 x 12' thd pump.

Pulled 61 joints 2-3/8 tubing , 2-3/8 seating nipple .

Rigged up Xcel wireline service set CIBP at 1830 ft.

Shut down.

Daily Cost.

H-D Well Service \$ 1,080.00

Xcel Wireline \$ 1,500.00

6-11-2020

Rigged up Bob's oil service water truck loaded 5-1/2 casing with fresh water pressured casing to 350 #'s

Held ok rigged H-D Well service down.

1:30 Met Ken With KCC. Ran CIT well passed.

Daily Cost.

H-D Well service \$ 480.00

BoB's Oil Service \$ 360.00

Rob.

August 12, 2021

Loveness Mpanje
F. G. Holl Company L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

Re: Temporary Abandonment
API 15-145-21561-00-01
BROCHER "A" 1-2
SE/4 Sec.02-21S-15W
Pawnee County, Kansas

Dear Loveness Mpanje:

Your temporary abandonment (TA) application for the well listed above has been approved. In accordance with K.A.R. 82-3-111 the TA status of this well will expire 08/11/2022.

Your exception application expires on 08/11/2023.

- * If you return this well to service or plug it, please notify the District Office.
- * If you sell this well you are required to file a Transfer of Operator form, T-1.
- * If the well will remain temporarily abandoned, you must submit a new TA application, CP-111, before 08/11/2022.

You may contact me at the number above if you have questions.

Very truly yours,

Michael Maier