



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100808

41004

INV 901200

TICKET NUMBER 55990 ✓

LOCATION Ocala, Ky.

FOREMAN Cory Davis

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-23-14	7158	Frusher #2	9	210	23 ^w	Hodgecosh
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Raymond oil			760	Kaleb C	703	Cory D
MAILING ADDRESS			566	Alex H		
PO BOX 48788						
CITY	STATE	ZIP CODE				
Wichita	KS	67201				

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 263 CASING SIZE & WEIGHT 8 7/8 23#
 CASING DEPTH 260 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 15.2 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 20'
 DISPLACEMENT 15 1/4 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting. Rig up on LD, circ casing on bottom
 mix 180 sks cem 3% cc 2% gal wash up + Displace 15 1/4 BBL shut in
 rig down

Cement Did Circle
 A Prot BBL to Apt

Thank You
 From Cory + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE 0471	1	PUMP CHARGE	1.150	1.150
✓ CE 0002	30	MILEAGE	7.15	214.50
✓ CE 0711	8.46	Ten Mileage Delivery min	1.75	660.00
5162 ✓ CC 5871	190 sks	Surface Blend II	24.00	4320.00
			Subtotal	6394.50
			25% Disc	1586.13
			Subtotal	4758.37 ✓
			SALES TAX	247.86
			ESTIMATED TOTAL	5006.23

Havin 3737

AUTHORIZATION

[Signature]

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

INV 901243
TICKET NUMBER 55078 ✓
LOCATION Oakley, KS
FOREMAN Jimmie Cottrell
Cory Davis
Walt Dinkel
KS

100884
41077

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-1-19 ✓	7158 ✓	Frusher 2 ✓	09	215	23 ⁰⁰	Noweman
CUSTOMER Raymond Oil Co ✓			NEAR CITY South to Rd X E 3 miles Sinto			
MAILING ADDRESS PO BOX 48788			TRUCK #	DRIVER	TRUCK #	DRIVER
CITY Wichita			753	Alex	1098	Walt
STATE KS			566	Kaleb	703	Cory
ZIP CODE 67201			T-129	Neil		
			697	Jimmie		
JOB TYPE	HOLE SIZE	HOLE DEPTH	CASING SIZE & WEIGHT			
Longstring DV Tool	7 7/8	4645	5 1/2 15.5 #			
CASING DEPTH	DRILL PIPE	TUBING	OTHER DV Tool @ 1538			
4643						
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING			
14.2/12.5						
DISPLACEMENT	DISPLACEMENT PSI	MIX PSI	RATE			
109/36.5						
REMARKS: Safety Meeting Rig up on LD Run Float Equipment Circ casing on bottom Pump 500 gal Mud flush mix 125 sacks Thixblend III wash pump & Lines Release Plug Displace 70 bbls H ₂ O 40 bbls Mud @ 1000 land plug @ 1400 Release Pressure Float Hold open DV Tool and circ Tool open @ 200 Mix 30 sks in Rathole mix 370 sks down casing wash Pump & Lines Release plug Displace 36.5 bbls H ₂ O @ 700 Land Plug @ 1700 Release Pressure to check tool Tool is closed Rig down CEMENT DID CIRCULATE						

Thank You
Jimmie & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0453	1	PUMP CHARGE	2800.00	2800.00
✓ CE0002	30	MILEAGE	7.15	214.50
✓ CE0710	24.97 (749.10)	Tan Mileage Delivery	1.75	1310.73
SNS ✓ CC5862	125 sks	Thixblend III	26.00	3250.00
✓ CC6077	200 625 lb	Kolseal	.50	312.50
SNS ✓ CC5831	1000 400 sks	Lightweight Blend VII	17.50	7000.00
✓ CC6075	200 lb	Floccal	3.00	600.00
SNS ✓ CC6125	500 gal	Mud Flush	.65	325.00
✓ CP8495	1	5 1/2 AFU Float Shoe	585.00	585.00
✓ CP8254	1	5 1/2 Latch Down Plug Assembly	400.00	400.00
✓ CP8576	13	5 1/2 Turbolizers	110.00	1430.00
✓ CP8629	3	5 1/2 baskets	385.00	1155.00
✓ CP8801	1	5 1/2 DV Tool	5970.00	5970.00
				25,352.93
			-25% Discount	6,338.23
				19,014.70 ✓
			SALES TAX	1206.45
			ESTIMATED TOTAL	20221.15

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.