




P. O. Box 466
Ness City, KS 67560
Off: 785-798-2300



Invoice

DATE	INVOICE #
8/24/2019	27751

BILL TO
Presley Operating LLC 101 Park Ave, Ste 670 Oklahoma City, OK 73102



- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#1-3	S.V.T.	Haskell	Murfin Rig #21	Oil	Development	Deep Surface	David E.

PRICE REF.	DESCRIPTION	QTY	UM	UNIT PRICE	AMOUNT
575D	Mileage - 1 Way	110	Miles	5.00	550.00
576D-D	Pump Charge - Deep Surface (> 500 Ft.) & Port Collars	1	Job	1,400.00	1,400.00
290	D-Air	7	Gallon(s)	42.00	294.00T
221	Liquid KCL (Clayfix)	2	Gallon(s)	25.00	50.00T
401-8	8 5/8" Insert Float Without Auto Fill	1	Each	210.00	210.00T
409-8	8 5/8" Turbolizer	3	Each	110.00	330.00T
410-8	8 5/8" Top Plug	1	Each	130.00	130.00T
194	Plug Container Rental	1	Each	200.00	200.00T
330	Swift Multi-Density Standard (MIDCON II)	700	Sacks	17.00	11,900.00T
276	Flocele	175	Lb(s)	3.00	525.00T
581D	Service Charge Cement	700	Sacks	1.85	1,295.00
583D	Drayage	3,845	Ton Miles	0.95	3,652.75
	Subtotal				20,536.75
	Sales Tax Haskell County (7.00%	954.73

JOINT INTEREST BILLING

Approved _____ Date _____
 Date To Be Paid _____
 LOE _____ IDC _____ EQ _____ LHC _____ TOP _____ ACP _____
 Description 71110 Surf Cmt
 Lease 57087
 Chk. No. _____ Date Paid _____
 JIB Date _____ WC _____

We Appreciate Your Business!

Total

\$21,491.48



CHARGE TO: Kresley Operating
 ADDRESS: _____
 CITY, STATE, ZIP CODE: _____

SERVICE LOCATIONS: 1. Hays KS 2. Ness City KS

WELL/PROJECT NO. 1-3 LEASE S.V.T COUNTY/PARISH Haskell STATE KS DATE 8-24-19 OWNER _____

TICKET TYPE SERVICE SALES CONTRACTOR Martin RIG NAME/NO. Rig 21 SHIPPED VIA not DELIVERED TO location ORDER NO. _____

WELL TYPE D/I WELL CATEGORY development JOB PURPOSE Deep Surface WELL PERMIT NO. _____ WELL LOCATION _____

REFERRAL LOCATION _____ INVOICE INSTRUCTIONS _____

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING		DESCRIPTION	MILEAGE	QTY.	UM	QTY.	UM	UNIT PRICE	AMOUNT
		LOC	ACCT								
575					Tax # 111	110	mi			5.00	550.00
576 D					Pump Charge - Deep Surf.	1	EA			1400.00	1400.00
290					D-Air	7	bar			42.00	294.00
221					Liquid Bar	2	bar			25.00	50.00
401					Insert Floor w/ Aero Fill	1	EA			210.00	210.00
409					Turbolizer	3	EA			110.00	330.00
410					TOP Plug	1	EA			130.00	130.00
194					Plug Containers Rental	1	EA			200.00	200.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

DATE SIGNED _____ TIME SIGNED _____ AM PM

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY: OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN? YES NO
 WE UNDERSTOOD AND MET YOUR NEEDS? YES NO
 OUR SERVICE WAS PERFORMED WITHOUT DELAY? YES NO
 WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY? YES NO
 ARE YOU SATISFIED WITH OUR SERVICE? YES NO

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES: The customer hereby acknowledges receipt of the materials and services listed on this ticket.

DATE SIGNED _____ TIME SIGNED _____ AM PM

SWIFT OPERATOR: David H. ... APPROVAL: _____

TOTAL: 21491.48

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 8-24-19 PAGE NO. 3

CUSTOMER		WELL NO.		LEASE		JOB TYPE		TICKET NO.	
Presley Operating		1-3		S.V.T		Deep Surf			
CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS	
				T	C	TUBING	CASING		
	330								On location
									Rtd - 1773
									Centralizers - 1, 3, 6
	530								START Running Csg
	725								Break Circ on Bottom
	800	5.5	20			200			Pump kcal spacer
		6	0			200			START CMT - 150 sks @ 11.8 PPG
		6	72			200			Raise wgt to 12.7 PPG for 350 sk
		5	200			200			Raise wgt to 13.5 PPG for 100 sk
		5	233			200			Raise wgt to 14.5 PPG for 100 sk
	905	5	259			200			END CMT
									Release Plug
	910	6	0			200			START Disp - CMT Circulating
	910	6	70			400			CATCH PSI
	925	5	111			800/1000			LAND plug
									Lift psi - 800 #
									LAND psi - 1000 #
									Shut in
									Job Complete
									Thanks
									Davis, Zach, Kirby & Preston
									★ Circulated 100 sks CMT TO THE PIT.