

Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3

Elevation: 1739 Sur Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

DATE August 13

2019

Formation: Lans A-F Test Interval: 2963 -Total Depth: 3061' 3061'

Time On: 00:49 08/13 Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

Electronic Volume Estimate: 2183'

1st Open Minutes: 45 **Current Reading:** 155" at 45 min

DST #1

Max Reading: 155" Max Reading: 0"

1st Close 2nd Open Minutes: 45 Minutes: 45 **Current Reading: Current Reading:** 0" at 45 min

215.3" at 45 min

Max Reading: 215.3" Max Reading: 0"


2nd Close

Minutes: 60

Current Reading:

0" at 60 min

Inside Recorder





Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3

Elevation: 1739 Sur Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

Total Depth: 3061'

DATE

August

13 2019

DST #1 Formation: Lans A-F Test Interval: 2963 -

3061'

Time On: 00:49 08/13 Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

Recovered

<u>Foot</u>	<u>BBLS</u>	Description of Fluid		
2834	40.32782	G		
111	1.57953	SLOCSLGCM		

Gas %	<u>Oil %</u>	Water %	Mud %
100	0	0	0
5	2	0	93


Total Recovered: 2945 ft

Total Barrels Recovered: 41.90735

Reversed	Out
NO	

Initial Hydrostatic Pressure	1378	PSI
Initial Flow	14 to 38	PSI
Initial Closed in Pressure	532	PSI
Final Flow Pressure	45 to 61	PSI
Final Closed in Pressure	662	PSI
Final Hydrostatic Pressure	1370	PSI
Temperature	113	°F
Pressure Change Initial	0.0	%
Close / Final Close		

Recovery at a glance



GIP cubic foot volume: 226.86396



Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

DST #1

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3 Elevation: 1739 Sur Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

DATE

August

13 2019

Formation: Lans A-F Test Interval: 2963 - Total Depth: 3061'

3061'

Time On: 00:49 08/13 Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

BUCKET MEASUREMENT:

1st Open: 1/2" Blow. BOB in 5 mins

1st Close: NOBB

2nd Open: BOB Instantly

2nd Close: NOBB

REMARKS:

Gas to Surface during the bleed out on the Final Shut in.

Tool Sample: 30% Gas 2% Oil 0% Water 68% Mud



Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

DST #1

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3 Elevation: 1739 Sur

Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

DATE

August 13

2019

Formation: Lans A-F

Test Interval: 2963 -

Total Depth: 3061'

3061'

Time On: 00:49 08/13

Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

Down Hole Makeup

Heads Up: 7.559999999999 FT **Packer 1:** 2957.83 FT

Drill Pipe: 2945.23 FT **Packer 2:** 2962.83 FT

ID-3 1/2

Top Recorder: 2949.83 FT

Weight Pipe: FT Bottom Recorder: 3033 FT

ID-2 7/8 Well Bore Size: 7 7/8

Collars: 0 FT

ID-2 1/4

Surface Choke: 1"

Test Tool: 26.16 FT Bottom Choke: 5/8"

ID-3 1/2-FH

Total Anchor: 98.17

Anchor Makeup

Packer Sub: 1 FT

Perforations: (top): 3 FT

4 1/2-FH

Change Over: 1 FT

Drill Pipe: (in anchor): 63.67 FT

ID-3 1/2

Change Over: .5 FT

Perforations: (below): 29 FT

4 1/2-FH



Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

DST #1

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3 Elevation: 1739 Sur Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

DATE August

13 2019

Formation: Lans A-F

Test Interval: 2963 -

Total Depth: 3061'

3061'

Time On: 00:49 08/13 Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

Mud Properties

Mud Type: Chem Weight: 8.6 Viscosity: 53 Filtrate: 8 Chlorides: 4000 ppm



Uploading recovery &

pressures

Company: RJM Oil Company,

Inc

Lease: Ames Unit #15

SEC: 35 TWN: 18S RNG: 11W

County: BARTON State: Kansas

Drilling Contractor: Southwind Drilling,

Inc - Rig 3 Elevation: 1739 Sur Field Name: Ames Pool: Infield Job Number: 381

API #: 15-009-26267-00-00

DATE August

13 2019 DST #1 Formation: Lans A-F Test Interval: 2963 - Total Depth: 3061'

Time On: 00:49 08/13 Time Off: 09:06 08/13

Time On Bottom: 03:41 08/13 Time Off Bottom: 06:56 08/13

Gas Volume Report

1st Open 2nd Open

Time	Orifice	PSI	MCF/D	Time	Orifice	PSI	MCF/D
				I			