



### #1 Wells-Whitham

2,029' FSL & 149' FWL

49' N & 181' W of NW NW SW Section 9-17S-36W

Wichita County, Kansas

API# 15-203-20358-0000

Elevation: GL: 3,287', KB: 3,295'

Sample Tops			Ref. Well
Anhydrite	2462	+833	-7
B/Anhydrite	2479	+816	-6
Stotler	3565	-270	+1
Heebner	3946	-651	-12
Toronto	3959	-664	-12
Lansing	3994	-699	-9
Muncie	4182	-887	-19
Stark	4262	-967	-8
Hush	4312	-1017	-7
BKC	4356	-1061	-10
Marmaton	4412	-1117	-20
Altamont	4426	-1131	-21
Pawnee	4504	-1209	-15
Myrick	4546	-1251	-17
Ft. Scott	4560	-1265	-18
Cherokee	4586	-1291	-18
Johnson	4674	-1379	-12
Morrow	4742	-1447	-18
Mississippian	4851	-1556	-19
RTD	4930	-1635	



PRESSURE PUMPING LLC  
 PO Box 884, Chanute, KS 66720  
 820-431-9210 or 800-467-8676

100557  
 40758

TICKET NUMBER 56053  
 LOCATION Oakley Ks.  
 FOREMAN Cory Davis

FIELD TICKET & TREATMENT REPORT  
 CEMENT

Invoice # 900892

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
5-28-19	7173	Well-Whitham #1	9	17S	36W	Wichita	
CUSTOMER		Pence Ks W to RD 15 4 miles S E. Side		TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS		Ritchie Explor.		731	Kaleb C.	1098	Walt D
P.O. Box 783188				70	Xavier C.	703	Cory D
Wichita		STATE	ZIP CODE	Halper	Alex H.		
		KS	67278-3188				

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 253 CASING SIZE & WEIGHT 8 5/8 24#  
 CASING DEPTH 253 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 20'  
 DISPLACEMENT 14.3/4 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting, rig down well, run casing to bottom, circ. casing. Hook up to pump truck mix 200SK; common 3% CC. 2% gal wash up + Displace 14.3/4 BBL H2O, Rig down

Cement did circ. 1 BBL to Pit  
 in Cellar

Thank you  
 from Cory & Crew.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE 0471	1	PUMP CHARGE	1.150 <sup>00</sup>	1.150 <sup>00</sup>
CE 0002	40	MILEAGE	7.15	286 <sup>00</sup>
CE 0711	9.4	Ton mileage Deliver min	1.75	660 <sup>00</sup>
CC 5871	200	Surface Blend II	24 <sup>00</sup>	4,800 <sup>00</sup>
			Subtotal	6,896 <sup>00</sup>
			25% Disc.	1,724 <sup>00</sup>
			Subtotal	5,172 <sup>00</sup>
			SALES TAX	306.00
			ESTIMATED TOTAL	5478.00

Rev'n 3737

AUTHORIZATION [Signature] TITLE [Signature] DATE 5-28-19

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are hereby accepted and confirmed on this form.





PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

100601  
40800

TICKET NUMBER 56034  
LOCATION Oakley, KS  
FOREMAN Jerry Y

FIELD TICKET & TREATMENT REPORT  
CEMENT

Invoice # 9009425

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-10-19	7173	Well - Whitham #1	9	17S	36W	Wichita
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
R. Tech Exp			760	Kaleb C		
MAILING ADDRESS			70	Alex H		
P.O. Box 783188			535	Jerry Y		
CITY	STATE	ZIP CODE				
Wichita	KS	67278-3188				

JOB TYPE Plug HOLE SIZE 7 7/8 HOLE DEPTH 4930 CASING SIZE & WEIGHT \_\_\_\_\_  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE 4 1/2 TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 13.8 SLURRY VOL 1.42 WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting & rig up on Well 12 plug as ordered with 280 sks  
60/40 48 1/4 # 10  
50 sks @ 2480'  
80 sks @ 1550'  
50 sks @ 775'  
50 sks @ 280'  
20 sks @ 60'  
30 RH

Thank you  
Jerry & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0451	1	PUMP CHARGE	1900.00	1900.00
CE0002	40	MILEAGE	7.15	286.00
CE0710	12.04	ton mileage delivery	1.75	842.80
CG5829	280 sks	lite blend IV	16.00	4480.00
CC6075	70 #	flashed	3.00	210.00
			Sub total	7718.80
			-25%	1929.70
			Sub total	5789.10
			SALES TAX	298.99
			ESTIMATED TOTAL	6088.09

SCANNED

Rayn 3737 AUTHORIZATION [Signature] TITLE Tool pusher DATE 6-11-19

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.