


Lease:	PAGE	
Owner:	S&K Oil	
OPR #:	33551	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 7"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 711 1/2' 2 7/8 8rd	Cemented: _____	Hole Size: 5 5/8



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 620-363-2696



Well #: I-2
Location: W2W2W2SES18T25SR22E
County: Bourbon
FSL: 1320
FEL: 2620
API#: 15-011-24640
Started: 9/10/2019
Completed: 9/11/2019
TD: 721'

SN: -----	Packer: -----
Plugged: -----	Bottom Plug: -----

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top soil (lose rock)	8	526	Light shale
6	8	Clay & Lime	5	531	Black shale
11	19	Shale	15	546	Shale
27	46	Lime	5	551	Black shale
3	49	Black shale	1	552	Lime
3	52	Lime	19	571	Shale
8	60	Shale	18	589	Light shale (Limey)
22	82	Lime	1	590	Lime
2	84	Shale	2	592	Black shale
3	87	Lime	3	595	Light shale
14	101	Shale	21	616	Shale
2	103	Lime	15	631	Black shale (Limey)
7	110	Shale (Black)	20	651	Light shale
25	135	Shale	20	671	Dark sandy shale
3	138	Lime	8	679	Shale
48	186	Shale	2	681	Sandy shale (Oil sand streak)
5	191	Light shale	3	684	Oil sand (some shale) (Fair bleed)
14	205	Black shale	3	687	Oil sand (some shale) (Good bleed)
5	210	Light shale	5	692	Oil sand (very little shale) (Good bleed)
31	241	shale	3	695	Oil sand (Good bleed) (Some shale)
9	250	Shale (Limey)	2	697	Oil sand (Very Shaley) (Fair bleed)
7	257	Lime	1	698	Sandy shale (Oil sand streak)
7	264	Shale (Limey)	12	710	Sandy shale
3	267	Red bed	TD	721	Shale
14	281	Light shale			
44	325	Sandy shale			
13	338	Shale			
1	339	Coal			
7	346	Light shale			
23	369	Lime			
2	371	Black shale			
33	404	Shale (Limey)			
9	413	Light shale			
8	421	Lime			
16	437	Shale			
4	441	Lime			
5	446	Light shale			
9	455	Sand (Light shale)			
2	457	Sandy shale (Slight odor)			
1	458	Oil sand (some shale) (Poor bleed)			
15	473	Sandy shale			
44	517	Shale			
1	518	Lime			