


Lease:	PAGE	
Owner:	S & K Oil	
OPR #:	33551	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 719' 2 7/8 8rd	Cemented: ----	Hole Size: 5 5/8



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 620-363-2696



Well #: I15
Location: N2NWSE18T25SR22
County: Bourbon
FSL: 2310
FEL: 1980
API#: 15-011-24645-00-00
Started: 8/28/2019
Completed: 8/29/2019
TD: 721'

SN: ----	Packer: ----
Plugged: ----	Bottom Plug: ----

## Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top soil (Lose rock)	1	461	Shale (Oil sand streak)
4	5	Clay	54	515	Shale
2	7	Lime	6	521	Black shale (Limey)
3	10	Black shale	35	556	Dark shale
3	13	Lime	10	566	Shale (Limey)
12	25	Shale	20	586	Light shale
4	29	Sandy shale	3	589	Black shale
26	55	Lime	17	606	Light shale
2	57	Black shale	5	611	Light sandy shale
4	61	Lime	15	626	Shale
9	70	Shale	30	656	Light shale
21	91	Lime	3	659	Black sand (odor)
14	105	Shale	20	679	Dark sandy shale
8	113	Black shale	2	681	Oil sand (Black sand streak) (poor bleed)
26	139	Shale	6	687	Oil sand (Good bleed)
5	144	Lime	3	690	Oil sand (Heavy bleed)
48	192	Shale	5	695	Oil sand (some shale) (Good bleed)
1	193	Black shale	4	696	Sandy shale (oil sand streak)
20	213	Shale	8	704	Sandy shale
4	217	Black shale	3	707	Oil sand (Some shale) (Very poor bleed)
16	230	Light shale	3	710	Sandy shale
4	234	Red bed	TD	721	Shale
21	255	Light shale			
9	264	Lime			
12	276	Light shale			
5	281	Red bed			
9	290	Light shale			
3	293	Sandy shale			
2	295	Sand (Dry)			
29	324	Sandy shale			SURFACE 8-28-2019
22	346	Shale			SET TIME - 12:00PM
3	349	Light shale			CALLED 11:15AM BROOKE
4	353	Coal			
23	376	Lime			
2	378	Black shale			
37	415	Dark shale			
16	431	Lime			
7	438	Black shale			
5	443	Lime			
3	446	Light shale			
8	454	Light sandy shale			
1	455	Sandy shale (Oil sand streak)			
5	460	Oil Sand (Some shale) (Good bleed)			