


Lease:	PAGE	
Owner:	S&K Oil	
OPR #:	55331	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 7"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 701' 2 7/8 8rd	Cemented: _____	Hole Size: 5 5/8"



Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056  
Cell # 620-363-2683  
Office # 620-363-2696



Well #: I-4
Location: W2W2NWSE18T25SR22E
County: Bourbon
FSL: 1980
FEL: 2620
API#:15-011-24642
Started: 9/05/2019
Completed: 9/09/2019
TD: 721'

SN: -----	Packer: -----
Plugged: -----	Bottom Plug: -----

## Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top soil (Lose rock)	21	554	Shale
8	10	Clay (Limey)	1	555	Lime
8	18	Shale	6	561	Shale
33	51	Lime	10	571	Light shale (Limey)
2	53	Black shale	8	579	Shale
5	58	Lime	2	581	Black shale
7	65	Shale	20	601	Light shale
22	87	Lime	25	626	Shale
14	101	Shale	18	644	Light shale
10	111	Black shale	10	654	Light shale (Limey)
23	134	Shale	17	671	Dark sandy shale (Slight odor)
25	159	Lime	6	677	Shale
46	205	Shale	4	681	Sandy shale (Oil sand streak) (Strong odor)
2	207	Black shale	3	684	Oil sand (some shale) (Fair bleed)
28	235	Light shale	4	688	Oil sand (some shale) (Good bleed)
4	239	Red bed	5	693	Sandy shale (Oil sand streak) (Poor bleed)
5	244	Light shale	3	696	Shale
7	251	Light shale	5	701	Dark sandy shale
8	259	Lime	5	706	Sandy shale (Oil sand streak)
12	271	Shale (Lime)	1	707	Oil sand (Shaley) (Fair bleed)
5	276	Red bed	4	711	Sandy shale
5	281	Light shale	TD	721	Shale
5	286	Sand			
50	336	Sandy shale			
5	341	Shale			
1	342	Coal			
9	351	Light shale			
20	371	Lime			
2	373	Black shale			
42	415	Shale			
14	429	Lime			
6	435	Shale			
8	443	Lime			
3	446	Shale			
7	453	Sandy shale			
1	454	Sandy shale (Oil sand streak) (Poor bleed)			
2	456	Oil sand (Shaley) (Fair bleed)			
4	460	Oil sand (some shale) (Good bleed)			
7	467	Sandy shale			
49	516	Shale			
5	521	Black shale (Limey)			
11	532	Shale			
1	533	Lime			