


Lease:	PAGE
Owner:	S&K Oil
OPR #:	55331
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 620-363-2696



Well #: I-13
Location: S2NWSE18T25SR22E
County: Bourbon
FSL: 1650
FEL: 1980
API#: 15-011-24639
Started: 9/03/2019
Completed: 9/04/2019

Surface: 20' of 7"	Cemented: 5 Sacks	Hole Size: 9 1/2"
Longstring: 686' 2 7/8" 8rd	Cemented: _____	Hole Size: 5" 5/8"

SN: -----	Packer: -----
Plugged: -----	Bottom Plug: -----

TD: 695'

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top soil (Lose rock)	15	524	Shale
23	24	Lime	2	526	Lime
2	26	Black shale	5	531	Black shale
9	35	Lime	19	550	Light shale
3	38	Shale	6	556	Shale
22	60	Lime	1	557	Lime
2	62	Shale	4	561	Light shale
3	65	Lime	3	564	Black shale
4	69	Shale	21	585	Shale
12	81	Sandy shale	6	591	Black shale
5	86	Black shale	10	601	Light shale
26	112	Shale	10	611	Light sandy shale
3	115	Lime	14	625	Light shale
71	186	Shale	10	635	Dark sandy shale
4	190	Black shale	21	656	Shale
11	201	Light shale	1	657	Oil sand (Very Shaley) (Poor Bleed)
4	205	Red bed	2	659	Oil sand (Some Shale) (Fair Bleed)
20	225	Shale	6	665	Oil sand (Good Bleed)
8	233	Lime	5.5	670.5	Oil sand (Some Shale) (Good Bleed)
13	246	Light shale	2.5	673	Sandy shale (Oil sand streak)
5	251	Red bed	3	676	Shale
38	289	Light sandy shale	5	681	Sandy Shale (Black sand streak)
18	307	Shale	TD	695	Shale
8	315	Light shale			
1	316	Coal			
5	321	Light shale			
22	343	Lime			
6	349	Black shale			
24	373	Shale			
2	375	Lime			
11	386	Light shale			
13	399	Lime			
2	401	Shale			
1	402	Lime			
6	408	Black shale			
4	412	Lime			
2	414	Shale			
11	425	Light shale (Limey)			
4	429	Oil sand (Very Shaley) (Poor Bleed)			
1	430	Sandy shale (Oil sand streak)			
58	488	Shale			
2	490	Lime			
19	509	Shale (Limey) (Dark)			