


Lease:	Swisher	
Owner:	S&K Oil	
OPR #:	33551	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 707' 2 7/8 8rd	Cemented: _____	Hole Size: 5' 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 620-363-2696



Well #: I13
Location: E2SWS18R22ET25S
County: Bourbon
FSL: 1320
FEL: 3300
API#: 15-011-24647
Started: 9/16/2019
Completed: 9/17/2019
TD: 721'

SN: -----	Packer: -----
Plugged: -----	Bottom Plug: -----

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top soil	1	459	Oil sand (some shale) (Poor bleed)
7	9	Clay & lime	2	462	Sandy shale (Oil sand streak)
2	11	Lime	1	463	Oil sand (Some streak) (fair bleed)
2	13	Black shale	2	465	Oil sand (shaley) (poor bleed)
15	28	Lime	1	466	Sandy shale (oil sand streak)
1	29	Shale	31	497	Sandy shale
26	55	Lime	59	556	Shale
1	56	Black shale	2	558	Lime
4	60	Lime	8	566	Black shale
8	68	Shale	29	595	Shale
23	91	Lime	1	596	Coal
17	108	Shale	19	615	Shale (Limey)
8	116	Black shale	6	621	Shale
21	137	Shale	5	626	Black shale
8	145	Lime	2	628	Light shale
70	215	Shale	1	629	Light sandy shale
1	216	Coal	17	646	Light shale
9	225	Light shale	2	648	Oil sand (very shaley) (poor bleed)
5	230	Shale (Limey)	6	654	Oil sand (some shale) (fair bleed)
11	241	Red Bed	3	657	Oil sand (some shale) (good bleed)
6	247	Shale	1	658	Sandy shale (Oil sand streak)
3	250	Lime	3	661	Sandy shale
5	255	Shale	15	676	Sandy shale (white sand streak)
10	265	Lime	12	688	Shale
5	270	Light shale (Limey)	4	692	Oil sand (shaley) (fair bleed)
5	275	Shale	4	696	Oil sand (very little shale) (good bleed)
6	281	Red Bed	2	698	Sandy (Shaley) (oil sand streak)
4	285	Light shale	2	700	Oil sand (very shaley) (fair bleed)
5	290	Sand (dry)	1	701	Sandy shale
41	331	Sandy shale (Sand streak)	3	704	Sandy shale (Oil sand streak) (poor bleed)
21	352	Shale	10	714	Sandy shale
1	353	Black shale	2	716	Shale
13	366	Lime	TD	721	Sandy shale
1	367	Shale			
8	375	Lime			
12	387	Black shale			
32	419	Shale			
16	435	Lime			
8	443	Shale			
3	446	Lime			
1	447	Black shale			
9	456	Light shale			
2	458	Sandy shale (Odor)			