


Lease:	Swisher	
Owner:	S&K Oil	
OPR #:	33551	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 747' 2 7/8 8rd	Cemented: _____	Hole Size: 5' 5/8"



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 620-363-2696

Well #: I14
Location: S2NESWT25SR22ES18
County: Bourbon
FSL: 1650
FEL: 3300
API#: 15-011-24648
Started: 9/11/2019
Completed: 9/16/2019
TD: 761'

SN: -----	Packer: -----
Plugged: -----	Bottom Plug: -----

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top soil (Lose rock)	3	465	Sandy shale
8	10	Lime	2	467	Oil sand (shaley) (fair bleed)
3	13	Black shale	1	468	Sandy shale (Oil sand streaks)
6	19	Lime	32	500	Sandy shale
2	21	Shale	56	556	Shale
36	57	Lime	1	557	Lime
2	59	Black shale	5	562	Shale black
5	64	Lime	39	601	Shale
5	69	Shale	9	610	Sandy shale
18	87	Lime	11	621	Shale
3	90	Shale	3	624	Black shale
5	95	Lime	17	641	Light shale
10	105	Shale	1	642	Sand (Shaley) (strong odor) (Poor bleed)
8	113	Black shale	4	646	Sand (strong odor)
25	138	Shale	1	647	Oil sand (gas sand streak) (Poor bleed)
9	147	Lime	3	650	Oil sand (fair bleed)
49	196	Shale	6	656	Oil sand (good bleed)
1	197	Coal	1	657	Oil sand (coal streak) (fair bleed)
19	216	Shale	2	659	Sandy shale (Oil sand streak) (poor bleed)
1	217	Coal	2	661	Shale
4	221	Light shale	4	665	Sandy shale (white sand streak)
5	226	Sandy shale	21	686	Shale
9	235	Shale	1	687	Sandy shale (oil sand streak)
6	241	Red bed	2	689	Oil sand (some shale) (good bleed)
10	251	Shale	4	693	Oil sand (good bleed)
13	264	Lime	2	695	Sandy shale (Oil sand streak)
11	275	Shale	3	698	Oil sand (shaley) (fair bleed)
11	286	Red bed	7	705	Sandy shale
5	291	Sand (dry)	1	706	Sandy shale (Oil sand streak)
40	331	Sandy shale (dry sand streaks)	3	709	Sandy shale
14	345	Shale	6	715	Sandy shale (Oil sand streaks)
1	346	Coal	10	725	Sandy shale (white sand streaks)
6	352	Shale	3	728	Oil sand (good bleed) (some shale)
24	376	Lime	5	733	Oil sand (shaley) (fair bleed)
2	378	Black shale	1	734	Sandy shale (oil sand streak)
41	419	Shale	4	738	Oil sand (shaley) (good bleed)
18	437	Lime	11	749	Sandy shale
5	442	Shale	TD	761	Sandy shale (black sand streaks)
5	447	Lime			
11	458	Light shale			
2	460	Sandy shale			
1	461	Sandy shale (oil and streaks)			
1	462	Oil sand (limey) (poor bleed)			