

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

TEMPORARY ABANDONMENT WELL APPLICATION

OPERATOR: License#
Name:
Address 1:
Address 2:
City: State: Zip:
Contact Person:
Phone:
Contact Person Email:
Field Contact Person:
Field Contact Person Phone:

API No. 15-
Spot Description:
Sec. Twp. S. R.
GPS Location: Lat, Long
Datum: NAD27, NAD83, WGS84
County: Elevation:
Lease Name: Well #:
Well Type: Oil, Gas, OG, WSW, Other
SWD Permit #: ENHR Permit #:
Gas Storage Permit #:
Spud Date: Date Shut-In:

Table with 7 columns: Conductor, Surface, Production, Intermediate, Liner, Tubing. Rows include Size, Setting Depth, Amount of Cement, Top of Cement, Bottom of Cement.

Casing Fluid Level from Surface: How Determined? Date:
Casing Squeeze(s): to w / sacks of cement, to w / sacks of cement. Date:
Do you have a valid Oil & Gas Lease? Yes No
Depth and Type: Junk in Hole at Tools in Hole at Casing Leaks: Yes No Depth of casing leak(s):
Type Completion: ALT. I ALT. II Depth of: DV Tool: w / sacks of cement Port Collar: w / sack of cement
Packer Type: Size: Inch Set at: Feet
Total Depth: Plug Back Depth: Plug Back Method:

Geological Date:

Table with 4 columns: Formation Name, Formation Top, Formation Base, Completion Information. Rows 1 and 2.

UNDER PENALTY OF PERJURY I HEREBY ATTEST THAT THE INFORMATION CONTAINED HEREIN IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE

Submitted Electronically

Do NOT Write in This Space - KCC USE ONLY
Date Tested: Results: Date Plugged: Date Repaired: Date Put Back in Service:
Review Completed by: Comments:
TA Approved: Yes Denied Date:

Mail to the Appropriate KCC Conservation Office:

Table with 2 columns: Office Address, Phone. Rows for District Office #1, #2, #3, #4.

Operating Report

Well	Cross WB B 4-17			STR	17-24S-17W	Cty	Edwards	State	Kansas
Well Type	OIL	Well Status	TA-NC	Location	E2 NE SE (1830 FSL 405 FEL)				
PBTD:		TD:	4,575	Pumper	Delmar Pentz 620-617-1169				
<hr/>									
Equip:				Surf Csg	8.25" OD, @ 725' w/ 175 sx.				
				Inter Csg					
				Prod Csg	4.5" OD, @ 4570' w/ 225 sx. Cmt. top @ 3470 by CBL.				
				Perfs	Cherokee 4357-90				
<hr/>									
PR	16'			Tbg Subs	1 x 2 3/8"				
Ponies	1-8' 3/4"			2 3/8 Tbg. Jts	2 1/16 Tbg. Jts				
1" Rods #		1" FG Rods #		2 7/8 Tbg. Jts	3 1/2 Tbg. Jts				
7/8" Rods #	16	7/8" FG Rods #		Tbg Pump	2 x 2 1/4 x 15 x 17'				
3/4" Rods #	157	3/4" FG Rods #		Oth Tbg					
5/8" Rods #				Packer					
Sinker Bars		SB Size		Mud Anchor					
Oth Rods				DH Comments					
Pump									

Date and Service Type

4/10/2020 Activity Type - CP-111
Denied CP-111; > 10 years shut-in time limit.

7/2/2020 Activity Type - CIT
7-1-20 HD Double drum pole got stuck going into location.
7-2-20 Bobs oilfield service catted rig into location. Rigged up and unpacked well head. Pled out 2 3/8" x 6' sub. Brtoke head loose. Rigged up Excel Wireline. Set CIBP at 4300'. Rigged Down Excel and HD. Put swedge and valve onto casing. In the afternoon rigged up Bobs oil high pressure water truck to the casing. Loaded the hole and pressured to 300#. Held tight for 30 minutes. Ken with the KCC passed the C.I.T. Rigged down Bob oil truck. Daily Costs HD \$\$750, Excel Wireline \$2500.00
Bobs Oil \$ NA Adam Apley

September 09, 2021

Loveness Mpanje
F. G. Holl Company L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

Re: Temporary Abandonment
API 15-047-21463-00-00
CROSS W.B. B 4-17
SE/4 Sec.17-24S-17W
Edwards County, Kansas

Dear Loveness Mpanje:

Your temporary abandonment (TA) application for the well listed above has been approved. In accordance with K.A.R. 82-3-111 the TA status of this well will expire 09/10/2022.

Your exception application expires on 09/10/2023.

- * If you return this well to service or plug it, please notify the District Office.
- * If you sell this well you are required to file a Transfer of Operator form, T-1.
- * If the well will remain temporarily abandoned, you must submit a new TA application, CP-111, before 09/10/2022.

You may contact me at the number above if you have questions.

Very truly yours,

Michael Maier