

# QUALITY WELL SERVICE, INC.

7187

Federal Tax I.D. # 481187368

Home Office 30060 N. Hwy 281, Pratt, KS 67124

Mailing Address P.O. Box 468

Office 620-727-3410

Fax 620-672-3663

Rich's Cell 620-727-3409

Brady's Cell 620-727-6964

Date	7-27-19	Sec.	29	Twp.	19	Range	9	County	Rice	State	KS	On Location		Finish	
Lease	Wallance	Well No.	11-29			Location	1.5 North of Chase East into								
Contractor	STEELING DRG Rig #4							Owner	To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.						
Type Job	Surface							Charge To	Pama OPERATING Co. Inc.						
Hole Size	12 1/4		T.D.	315			Depth	311.							
Csg.	8 5/8		Depth												
Tbg. Size			Depth												
Tool			Depth												
Cement Left in Csg.			Shoe Joint	42.50			The above was done to satisfaction and supervision of owner agent or contractor.								
Meas Line			Displace	18.2			Cement Amount Ordered	210 sx 60/40 2% Gel							
<b>EQUIPMENT</b>							3% cc 1/2 lb cello flake								
Pumptrk	8	No.					Common	126							
Bulktrk	10	No.					Poz. Mix	84							
Bulktrk		No.					Gel.	362 #							
Pickup		No.					Calcium	543 #							
<b>JOB SERVICES &amp; REMARKS</b>							Hulls								
Rat Hole							Salt								
Mouse Hole							Flowseal 97 #								
Centralizers							Kol-Seal								
Baskets							Mud CLR 48								
D/V or Port Collar							CFL-117 or CD110 CAF 38								
Run 7jts 8 5/8 csg 23#							Sand								
Break circulation with Rig							Handling 230								
Pumped 10bbls H2O mixed 210 sx							Mileage 35								
60/40 2% Gel 3% cc 1/2 lb cello flake							<b>FLOAT EQUIPMENT</b>								
Shut down released plug displaced							Guide Shoe								
18.2 bbls H2O. Shut in 200psi							Centralizer								
cement circulated to surface.							Baskets								
							AFU Inserts								
							Float Shoe								
							Catch Down 8 5/8 Wooden Plug								
							LMV 35								
							Service Supervisor								
							Pumptrk Charge Surface								
							Mileage 70								
												Tax			
												Discount			
												Total Charge			
X Signature <i>Harry A. Salas</i>															

# QUALITY WELL SERVICE, INC.

7191

Federal Tax I.D. # 481187368

Home Office 30060 N. Hwy 281, Pratt, KS 67124

Mailing Address P.O. Box 468

Office 620-727-3410

Fax 620-672-3663

Rich's Cell 620-727-3409

Brady's Cell 620-727-6964

Date	8-3-19	Sec.	29	Twp.	19S	Range	9W	County	RICE	State	KS	On Location		Finish	
Lease	WALLACE	Well No.	11-29			Location CHASE R3 1 N E. Sinto									
Contractor	STERLING RIG #4				Owner		To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.								
Type Job	5 1/2 L.S.				T.D.		3750								
Hole Size	7 7/8				Depth		3333								
Csg.	5 1/2 14"				Charge To		RAMA OPERATING CO. INC.								
Tbg. Size					Street										
Tool					City		State								
Cement Left in Csg.	32				Shoe Joint		32								
Meas Line					Displace		80.54								
EQUIPMENT							10% SALT 5 1/2 ROSEAL 1/4" SCS PS								
Pumptrk	9	No.					Common 175 SX								
Bulktrk	10	No.					Poz. Mix								
Bulktrk		No.					Gel. 330 #								
Pickup		No.					Calcium								
JOB SERVICES & REMARKS							Hulls								
Rat Hole	30				Salt		966 #								
Mouse Hole	20				Flowseal		44 #								
Centralizers	3-5-10-12-14				Kol-Seal		878 #								
Baskets	2				Mud CLR 48		500 GAL								
D/V or Port Collar					CFL-117 or CD110 CAF 38		- CC-1 7 GAL								
Run 94 ft's 5 1/2 14" CSG SET @ 3333							Sand								
START CSG CSG ON Bottom Hook up to CSG							Handling 216								
Back circ w/ rig DRIP SET PKR 1000"							Mileage 35 / 7560								
Circ w/ rig							5 1/2 FLOAT EQUIPMENT								
START Pumping 6 Bbls 12 Bbls MP 6 4 1/2 H2O							Guide Shoe 1 EA HEAD & MANIFOLD								
START Plug R.M 16/65 50 SX							Centralizer 5								
START Mix! Pump 125 SCS CSG 1/4 B 1/4 GAL							Baskets 1								
SHUT DOWN Washup tek 1 RELEASE LD Plug							AFU Inserts								
START DISP W/ 2% KEL							Float Shoe 1 EA PKR SHOE BSET TYPE								
Lift PSI 700" 67 out							Latch Down 1 EA								
Land Plug 30 1/2 out 1100 #							SERVICE Supv 1 EA								
Pick up on CSG 1500 #							LMV 35								
RELEASE? HELD 1/4 Bbl BACK							Pumptrk Charge LS								
							Mileage 70								
							Tax								
							Discount								
							Total Charge								
Thank you PLEASE CALL AGAIN							3272.26								
TODD TJ JAKE															
X Signature															