



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1001376	1718	07/08/2019
INVOICE NUMBER			
93004693			

Pratt (620) 672-1201
 B F.G. HOLL COMPANY LLC
 I PO Box: 308
 L ELLINWOOD
 L KS US 67526
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME CALCARA 4-19
 O LOCATION
 B COUNTY BARTON
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

PAID
 SEP 30 2019
 BY 80992

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41182361	19572		Net - 30 days	08/07/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 07/06/2019 to 07/06/2019</i>				
0041182361				
171819527L Cement-New Well Casing/Pi 07/06/2019 CEMENT SURFACE CASING				
A-Con Blend	175.00	EA	244878	
Class C Cement	175.00	SK		
Celloflake	88.00	LB		
Calcium Chloride	825.00	LB		
Light Vehicle Mileage	65.00	MI		
Heavy Equipment Mileage	130.00	MI		
Plug Container Utilization Charge	1.00	EA		
Depth Charge, 0'-1000'	1.00	HR		
Blending & Mixing Service Charge	350.00	SK		
Top Rubber Cement Plug, 8 5/8"	1.00	EA		
Centralizer 8 5/8 x 12 1/4	3.00	EA		
Baffle Plate Aluminum, 8 5/8" (Blue)	1.00	EA		
Service Supervisor Charge	1.00	EA		
Driver Charge	3.00	EA		

RECEIVED
 ROB LONG

105-1050

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL
DALLAS, TX 75284-1903	FORT WORTH, TX 76102	



1700 S. Country Estates Road
 Liberal, KS 67901
 PH (620)-624-2277 FAX (620) 624-2280

SERVICE ORDER - 1718 19572 L

Date: 7/6/2019

77MM 88 Hours.

Well Name:
 Calçara #4-19
 County - State:
 Barton, Ks

Location:
 19,19,14
 RRC #:

Type Of Service:
 Z42 - Cement Surface Casing

Customer's Order #:
 19572-28

Customer: FG Holl

1001376-2000964

Address: *PO Box 308
 Gilman Wood KSL 7526*

As a consideration, the above named Customer agrees to pay Basic Energy Services in accord with this rates and terms stated in Basic Energy Services current price list. Invoices are payable NET 30 (SEE 10.2) after date of invoice. Upon Customer's default in payment of Customer's account by such date, Customer agrees to pay interest thereon after default at 18% per annum. In the event it becomes necessary to employ an attorney to enforce collection of said account, Customer agrees to pay all the collection costs and attorney fees. These terms and conditions shall be governed by the laws of the state where services are performed or equipment or materials are furnished.

Basic Energy Services, warrants only title to the products, supplies and materials and that the same are free from defects in workmanship. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Basic Energy Services, liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, product liability, breach of warranty or otherwise) arising out of the sale or use of any products, supplies, or materials upon their return to Basic Energy Services, is expressly limited to the replacement of such products, supplies or materials or, at Basic Energy Services' option, to the advance to the Customer of credit for the cost of such items. In no event shall Basic Energy Services be liable for special, indirect, punitive or consequential damages.

CODE	QTY	UOM	DESCRIPTION	PRICE	TOTAL
BC118	175	EA	A-Con Blend		
BC101	175	SK	Class C Cement		
CC102	88	LB	Celloflake		
CC108	825	LB	Calcium Chloride		
ME101	65	MI	Light Vehicle Mileage		
ME102	130	MI	Heavy Equipment Mileage		
CE504	1	EA	Plug Container Utilization Charge		
CC1	1	HR	Depth Charge, 0'-1000'		
CE240	350	SK	Blending & Mixing Service Charge		
CF105	1	Ea	Top Rubber Cement Plug, 8 5/8"		
CF1773	3	Ea	Centralizer 8 5/8 x 12 1/4		
CF763	1	Ea	Baffle Plate Aluminum, 8 5/8" (Blue)		
BE143	1	Ea	Supervisor		
BE144	3	Ea	Driver		

PUMP TRUCK NUMBER: 37223 19572
 DRIVER: *Josme Torres*
Victor A. Cruz
 BASIC ENERGY SERVICES

THIS JOB WAS SATISFACTORILY COMPLETED
 OPERATION OF EQUIPMENT WAS SATISFACTORY
 PERFORMANCE OF PERSONEL WAS SATISFACTORY
Dim Vasquez
 CUSTOMER OR HIS AGENT

TO

Customer Comments or Concerns:
Order Change
Joe Martinez



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

Job Log

Customer:	FG Holl	Cement Pump No.:	37223 19572 28HRS	Operator TRK No.:	78868
Address:		Ticket #:	1718 19527 L	Bulk TRK No.:	37725 19827 Oscar
City, State, Zip:		Job Type:	Z42 - Cement Surface Casing		
Service District:	1718-Liberal KS	Well Type:	OIL		
Well Name and No.:	Calcara #4-19	Well Location:	19,19,14	County:	Barton
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-Con Blend Common	175	3% Calcium Chloride, .25pps Celloflake	37725 19827 Oscar	Front	Back
Premium Plus Cement	175	2% Calcium Chloride, .25pps Celloflake	37725 19827	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	12	2.47	14.49	432.25	TT Man Hours:	88
Tail:	14.8	1.34	6.33	234.5	# of Men on Job:	4

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
20:00pm							Arrived at location
10:00am							Spot trucks/ Rig up
14:30pm							Safety meeting
14:48pm						1500	Pressure test lines to 1500psi
14:49pm	3	10				50	Pump 10bbbls of fresh water spacer
14:52pm	5	76				100	Pump 76bbbls of lead from 175sks at 12lbs
15:08pm	5	41				50	Pump 41bbbls of tail from 175sks at 14.8lbs
15:21pm							Shut down/Drop plug/Wash pump and lines
15:23pm							Start Displacement of bbls with fresh water
15:31pm	5	20				20	20bbls gone
15:35pm	5	40				180	40bbls gone /Slow down rate
15:38pm	3	52				700	Bump plug/Hold for 5 minutes
							Release pressure to check if float holds
							Float did not hold close valves left head
							Got 40bbls of cement to Surface
							Rig Down
							Job Completed
							Thanked company man and rig crew

Size Hole	12 1/4	Depth	865.08		TYPE	
Size & Wt. Csg.	8 5/8 24#	Depth	865.08	New / Used	Baffle Plate	822.48
Landing Psi	500+	Depth			Retainer	Depth
Shoe Joint	42.6	Type			Perfs	CIBP

Customer Signature: <i>Adrian Vazquez</i>	Basic Representative:	Victor A. Corona
	Basic Signature:	<i>Victor A. Corona</i>
	Date of Service:	7/6/2019