



DRILLING COMPANY, INC.
WICHITA, KANSAS

Current Wellbore Configuration



8-5/8", 22# set at 287'
Cmt to surf w/325 sx.

Top of cement at 2720' (CBL 7/22/10)

LKC I perms at 3382'-3386'
LKC J perms at 3395'-3399'
LKC K perms at 3414'-3416'
LKC L perms at 3438'-3446' & 3452'-3456'
Arbuckle perms at 3468'-3508'

PBTD 3522'
RTD 3580'

5-1/2", 14 # csg set at 3571'. Cmt w/125 sx. 50/50 Pozmix.

Date:	9/27/2019
Well Name:	Hall D #2-17
Location:	345' FNL & 1147' FEL
	17-21S-12W
County:	Stafford
State:	KS
API:	15-185-23629
KB:	1868'
GL:	1857'
Spud Date:	7/1/2010