



WF

SEP 16 2019

PAGE	CUST NO	YARD #	INVOICE DATE
1 of 2	1000335	1718	09/11/2019
INVOICE NUMBER 93046149			

Pratt (620) 672-1201
 B BEREEXO LLC
 I 2020 N BRAMBLEWOOD
 L WICHITA
 L KS US 67206
 T
 O ATTN: VICKEY LOVETTE

J LEASE NAME ARROYO 22-6
 O LOCATION
 B COUNTY STANTON
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41189730	19572		Net - 30 days	10/11/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 09/10/2019 to 09/10/2019</i>				
0041189730				
171819689L Cement-New Well Casing/Pi 09/10/2019 CEMENT 2-STAGE PRODUCTION				
A-Serv-Lite	125.00	SK	9.88	1,235.00
AA2 Premium Cement	285.00	SK	7.22	2,057.70
A-Serv Lite	420.00	SK	9.88	4,149.60
AA2 Premium Cement	50.00	SK	7.41	370.50
Computerized Liquid Chemical Additive Un	50.00	HR	10.14	507.00
C-41P	79.00	LB	1.56	123.24
Celloflake	149.00	LB	1.56	232.44
C-17	158.00	LB	9.36	1,478.88
Gypsum	1,575.00	LB	0.39	614.25
Gilsonite	1,675.00	LB	0.39	653.25
1856 LBS Salt	1.00	LB	371.20	371.20
Light Vehicle Mileage	60.00	MI	1.95	117.00
Heavy Equipment Mileage	240.00	MI	3.12	748.80
Ton Mileage	2,502.00	MI	1.17	2,927.34
Blending & Mixing Service Charge	1.00	SK	511.50	511.50
Depth Charge, 5001-6000'	1.00	HR	1,131.00	1,131.00
Additional Stage Charge	1.00	HR	842.40	842.40
Plug Container Utilization Charge	1.00	EA	97.50	97.50
DATA ACQUISITION / STRIP CHART	1.00	LB	136.50	136.50
5 1/2" Float Shoe(Blue)	1.00	EA	425.00	425.00
5 1/2" Latch-Down Plug & Assembly (Red)	1.00	EA	850.00	850.00
Two Stage Cement Collar, 5 1/2" (Red)	1.00	EA	6,100.00	6,100.00
5 1/2" Basket (Blue)	3.00	EA	290.00	870.00
Turbolizer, 5 1/2" (Blue)	22.00	EA	110.00	2,420.00



PAGE	CUST NO	YARD #	INVOICE DATE
2 of 2	1000335	1718	09/11/2019
INVOICE NUMBER			
93046149			

Pratt (620) 672-1201
BEREXCO LLC
2020 N BRAMBLEWOOD
WICHITA
KS US 67206
ATTN: VICKEY LOVETTE

J LEASE NAME ARROYO 22-6
O LOCATION
B COUNTY STANTON
S STATE KS
I JOB DESCRIPTION Cement-New Well Casing/Pi
T JOB CONTACT
E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41189730	19572		Net - 30 days	10/11/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	4.00	EA	35.00	140.00

ACP
per bed

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	29,185.10
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	856.69
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	30,041.79
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



1700 S. Country Estates Road
 Liberal, KS 67901
 PH (620)-624-2277 FAX (620) 624-2280

SERVICE ORDER - 1718 19689 L

Date: 9/10/2019

TTMH 18 hours

Well Name: Arroyo # 22-6
 County - State: Stanton, Kansas
 Type Of Service: Z-42 Cement 2- Stage *Production*
 Customer: Berexco LLC

Location: 22 - 29S - 41W
 RRC #: *19572-28*
 Customer's Order #: *1000335*

Address: 2020 N. Bramblewoos
 Wichita, Kansas 67206-1094

As a consideration, the above named Customer agrees to pay Basic Energy Services in accord with the rates and terms stated in Basic Energy Services current price lists. Invoices are payable NET 30 (SEE 10.2) after date of invoice. Upon Customer's default in payment of Customers account by such date, Customer agrees to pay interest thereon after default at 18% per annum. In the event it becomes necessary to employ an attorney to enforce collection of said account, Customer agrees to pay all the collection costs and attorney fees. These terms and conditions shall be governed by the laws of the state where services are performed or equipment or materials are furnished.

Basic Energy Services, warrants only title to the products, supplies and materials and that the same are free from defects in workmanship. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Basic Energy Services, liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, product liability, breach of warranty or otherwise) arising out of the sale or use of any products, supplies, or materials upon their return to Basic Energy Services, is expressly limited to the replacement of such products, supplies or materials or, at Basic Energy Services, option, to the allowance to the Customer of credit for the cost of such items. In no event shall Basic Energy Services be liable for special, indirect, punitive or consequential damages.

CODE	QTY	UOM	DESCRIPTION	PRICE	TOTAL
BC119	125	SK	A-Serv Lite	26.00	3250.00
BC145	285	SK	AA2 Premium Cement	19.00	5415.00
BC119	420	SK	A-Serv Lite	26.00	10920.00
BC145	50	SK	AA2 Premium Cement	19.00	950.00
BC119	50	SK	A-Serv Lite	26.00	1300.00
CC105	79	LB	C-41P	4.00	316.00
CC102	149	LB	Celloflake	4.00	596.00
CC187	158	LB	C-17	24.00	3792.00
CC113	1575	LB	Gypsum	1.00	1575.00
CC201	1675	LB	Gilsonite	1.00	1675.00
CC111	1856	LB	Salt	0.50	928.00
ME101	60	MI	Light Vehicle Mileage	5.00	300.00
ME102	240	MI	Heavy Equipment Mileage	8.00	1920.00
TM	2502	MI	Ton Mileage	3.00	7506.00
CE240	930	SK	Blending & Mixing Service Charge	1.40	1302.00
CC6	1	HR	Depth Charge, 5001-6000'	2900.00	2900.00
CE409	1	HR	Additional Stage Charge	2160.00	2160.00
CE504	1	EA	Plug Container Utilization Charge	250.00	250.00
CC505	1	EA	Data Acquisition / Strip Chart	350.00	350.00
CF851	1	Ea	5 1/2" Float Shoe (Blue)	425.00	425.00
CF601	1	Ea	5 1/2" Latch Down Plug & Assembly (Red)	850.00	850.00
CF401	1	Ea	Two Stage Cement Collar, 5 1/2" (Red)	6100.00	6100.00
CF1901	3	Ea	5 1/2" Basket (Blue)	290.00	870.00
CF1651	22	Ea	Turbolizer, 5 1/2" (Blue)	110.00	2420.00
BE143	1	Ea	Supervisor	75.00	75.00
BE144	4	EA	Driver	35.00	140.00
				Book Total:	\$58,285.00
				Taxes:	
				Disc. Price:	\$29,185.10

PUMP TRUCK NUMBER: 37223 19572

DRIVER: *Gregal Echevarria*
Victor A. Corne
 BASIC ENERGY SERVICES

THIS JOB WAS SATISFACTORILY COMPLETED YES NO
 OPERATION OF EQUIPMENT WAS SATISFACTORY
 PERFORMANCE OF PERSONEL WAS SATISFACTORY

Jose Martinez
 CUSTOMER OR HIS AGENT

JB ALS

Customer Comments or Concerns:
Kerby Harp
Osac Chance / Jose Martinez



BASIC
ENERGY SERVICES

Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING



Job Log

Customer:	Berexco LLC	Cement Pump No.:	37223 19572 28HRS	Operator TRK No.:	78868
Address:	2020 N. Bramblewoos	Ticket #:	1718 19689 L	Bulk TRK No.:	19827 37725 Oscar 37712 19883 Kirby
City, State, Zip:	Wichita, Kansas 67206-1094	Job Type:	Z-42 Cement 2- Stage		
Service District:	1718-Liberal Ks	Well Type:	NEW		
Well Name and No.:	Arroyo # 22-6	Well Location:	22 - 29S - 41W	County:	Stanton State: Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
A Serv Lite	125	.25pps Celloflake	19827 37725 Oscar	Front	Back
AA-2 Premium Cement	285	10% Gypseal, 10% Salt, 5pps Gilsonite, .25pps Defoamer	37712 19883 Kirby	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	12.6	1.89	10.29	236.25	TT Man Hours:	118
Tail:	14.8	1.51	6.65	430.35	# of Men on Job:	4

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(Psi)		Description of Operation and Materials
			T	C	Tubing	Casing	
17:30pm							Arrived at location
23:00pm							Spot trucks/Rig up
2:45am							Safety meeting
3:06am						2500	Pressure test lines to 2500psi
3:09am	3	10				300	Pump 10bbls of fresh water spacer
3:13am	6	42				500	Pump 42bbls of lead from 125sks at 12.6lbs
3:23am	6	76				300	Pump 76bbls of tail from 285sks at 14.8lbs
3:55am							Shut down/Drop plug/Wash pump and lines to pit
4:00am							Start dispalcement of 135.8bbls (60bbls with water/las 75.8bbls with mud)
4:03am	8	20				500	20bbls gone water
4:05am	10	40				600	40bbls gone water
4:08am	8	60				300	60bbla gone water
4:11am	10	80				1200	80bbls gone mud
4:13am	8	100				1000	100bbls gone mud
4:16am	6	120				600	120bbls gone mud
4:18am	5	135				2000	Bump plug/Hold for 3 minutes
4:21am							Release pressure to check if float holds
4:25am						950	Drop opening tool and open dv tool
							Wait for 4 hours to start second stage
Size Hole	7 7/8	Depth	5750				TYPE
Size & Wt. Csg.	5 1/2 15.5#	Depth	5750	New / Used			Latch Down 5707 Depth
Landing Psi	500psi	Depth					DV Tool 3205 Depth
Shoe Joint	43	Type					Perfs CIBP

Customer Signature: 	Basic Representative:	Victor A. Corona
	Basic Signature:	
	Date of Service:	9/10/2019



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Berexco LLC	Cement Pump No.:	37223 19572 28HRS	Operator TRK No.:	78868
Address:		Ticket #:	1718 19689 L	Bulk TRK No.:	19827 37725 Oscar 37712 19883 Kirby
City, State, Zip:		Job Type:	Z-42 Cement 2- Stage		
Service District:	1718-Liberal	Well Type:	NEW		
Well Name and No.:	Arroyo # 22-6	Well Location:	22 - 29S - 41W	County:	Stanton
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
A Serv Lite	420	.25pps Celloflake	19827 37725 Oscar	Front	Back
AA-2 Premium Cement	50	10% Gypseal, 10% Salt, 5pps Gilsonite, .25pps Defoamer	37712 19883 Kirby	Front	Back
A Serv Lite	50	.25pps Celloflake		Front	Back

Lead/Tail:	Weight #1 Gal.	Yield	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	12.6	1.89	10.29	793.8	TT Man Hours:	118
Tail:	14.8	1.51	6.65	75.5	# of Men on Job:	4

Time (am/pm)	BPM	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
							Start Pumping 2nd Stage
							Safety meeting
9:07am	3	16.8				zero	Pump 16.8bbbs from 50sks for rat and mose Hole at 12.6lbs
9:19am	7	141.3				300	Pump 141.3bbbs of lead from 420sksk at 12.6lbs
9:41am	7	13.4				300	Pump 13.4bbbs of tail from 50sks at 14.8lbs
9:45am							Shut down/Drop plug/Wash pump an lines
9:53am							Start Displacement of 76bbbs with fresh water
9:57am	8	20				400	20bbbs gone
9:59am	8	40				700	40bbbs gone
10:02am	7	60				1000	60bbbs gone
10:03am	4	66				900	66bbbs gone/Slow down rate
10:06am	2	76				1820	Bump plug/Hold for 3 minutes
10:09am							Release pressure to check if float holds
							Rig down
							Job completed
							Thanked company man and rig crew

Size Hole	7 7/8	Depth	5750		TYPE	DV Tool	
Size & Wt. Csg.	5 1/2 15.5#	Depth	5750	New / Used	DV Tool	3205	Depth
Landing psi	1000+	Depth	0		Retainer		Depth
Top Plugs		Type			Perfs		CIBP

Customer Signature:		Basic Representative:	Victor A. Corona
		Basic Signature:	
		Date of Service:	9/10/2019

Berexco LLC
Arroyo 22-6/1st stage
5 1/2 Production
9/10/2019

