

QUALITY WELL SERVICE, INC.

7222

Federal Tax I.D. # 481187368
 Home Office 30060 N. Hwy 281, Pratt, KS 67124
 Mailing Address P.O. Box 468

lmw
C-2140

Office 620-727-3410
 Fax 620-672-3663

Rich's Cell 620-727-3409
 Brady's Cell 620-727-6964

Date	Sec.	Twp.	Range	County	State	On Location	Finish
9-10-19	23	29S	15W	PRATT	Ks		
Lease Cambrie		Well No. 3		Location CROFT Ks S to 100 th Rd 1/4 E on 100 th rd			
Contractor STEELING OLE RIA #4				Owner S. into			
Type Job 5 1/2 S				To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size 7 7/8		T.D. 4880'		Charge To Guffin			
Csg. 5 1/2 17"		Depth 4874.11		Street			
Tbg. Size		Depth		City State			
Tool		Depth		City State			
Cement Left in Csg. 21.17		Shoe Joint 21.17		The above was done to satisfaction and supervision of owner agent or contractor.			
Meas Line		Displace 112.59		Cement Amount Ordered 200 x PROC 2% FEL			
EQUIPMENT				10% Salt 5 1/2 x Koseal .6% C16A 25% C41P 1/4" PS			
Pumptrk 8 No.				Common 200 x			
Bulktrk 10 No.				Poz. Mix			
Bulktrk No.				Gel. 376"			
Pickup No.				Calcium			
JOB SERVICES & REMARKS				Hulls			
Rat Hole 30 x				Salt 1101"			
Mouse Hole 20 x				Flowseal 50"			
Centralizers 1-3-5-7-9-11				Kol-Seal 1000"			
Baskets				Mud CLR 48 500 GAL			
D/V or Port Collar				CFL-117 or CD110 CAF 38 C16A 1128"			
Ran this 5 1/2 17" Csg set				Sand CC-1 9 GAL C41P 47"			
START Csg Csg on Bottom TAG Hook up to Csg & BREAK CIRC W/ RIG DROP BALL CIRC W/ RIG				Handling 240			
				Mileage 251 6150			
				5 1/2 FLOAT EQUIPMENT			
START Pumping 6 Blk H ₂ O 12 Blk MF 6 Blk HR				Guide Shoe HEAD & MANIFOLD			
START Mirk Pump 50 x PLUG R M HOLES				Centralizer 6 EA			
START Mirk Pump 150 x Csg d 14.8" / GAL				Baskets			
SHOT DOWN wash up trk & RELEASE LD PLUG				AFU Inserts			
START Disp w/ 2% KCL				Float Shoe 1 EA			
LIFT PS. 96. out 700 #				Latch Down 1 EA			
PLUG DOWN 112.59 1100 #				SERVICE SUP 1 EA			
PS. up on Csg 1600 #				LMV 25			
Release & HELD 1/2 Blk BACK				Pumptrk Charge LS			
Good circ thru JOB				Mileage 50			
Thank you PLEASE CALL AGAIN TOM JAYE							
X Signature <i>J. H.</i>				Tax			
				Discount			
				Total Charge			