

EDISON OPERATING COMPANY, LLC

Kuhn #1-17

1829' FSL & 1451' FEL Sec 17-19S-12W

Barton Co., Kansas

1874' GL

1884' KB

Report – Set 8-5/8” surface

10-30-19 7:00 am, MIRU Southwind Drilling Rig #1, start spudding @ 2:30 pm 10-29-19. Cut 392' of 12 1/4" hole w/ survey @ 392' – 3/4 °. Run 9 jts of new 8-5/8" 24# csg, tallied 379.02', set @ 392'. RU Basic Energy, LLC, cement w/ 250 sx 60/40 poz 3% cc, 2% gel & 1/4 #/sx floccell. Cement did circulate w/ 25 sx to pit, plug down @ 6:30 am 10-30-19. WOC 8 hrs, Will drill plug @ 2:30 pm 10-30-19 then drill ahead.