

JOB LOG

SWIFT Services, Inc.

DATE 7-26-19 PAGE NO.

CUSTOMER Mull Drilling WELL NO 1-4 LEASE Constock OWINO JOB TYPE Long String TICKET NO. 27635

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1530							On location
								4 1/2 csg
								Rtd - 4750
								Shoe - 41.62
								Centralizers - 1, 2, 3, 4, 5, 7, 9
	1720							Start Running Csg
	2050							Break Circ on Bottom
	2200	2.5	8			0		Plug Rat Hole - 30 sks
		2.5	4			0		Plug Mouse Hole - 20 sks
						1400		- J Set pkr shoe
	2240	5.5	15			300		pump Gel spacer
		5.5	24			300		pump Flogcheck - 1000 GAL
		5.5	5			300		pump Gel spacer
	2245	5.5	0			300		START CRT - 200 sks @ 13.3 <sup>PPG</sup>
		5.5	50			150		END CRT
	2255							Drop plug/wash P & L
	2300	6.5	0			200		START Disp
		6.5	45			300		CATCH CRT
		6.5	60			500		Displacing
	2315	5.5	75			800/1400		LAND Plug - lift psi - 800 LAND psi - 1400
								Release Psi - Dry
								Job Complete
								Thanks DAVID, ZACH & Kirby

#32382