

JOB LOG

SWIFT Services, Inc.

DATE 8-16-19 PAGE NO. 1

CUSTOMER Mull Drig. Co. WELL NO. 1-4 OWWO LEASE COMSTOCK JOB TYPE SQUEEZE TICKET NO. 032173

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1000							ON LOCATED
								2 3/8 x 4 1/2 # 10.5
								PERFS = 4578 - 83
								PKR = 4473
	1000		4 1/2		✓		500	PSE ANNULUS - HELD - SHUT IN
	1015	1 1/2	7	✓		600		ZIT RATE
	1025	1 1/2	16	✓		400		MAX 75 SKS STANDARD CEMENT - 30 SKS w/ HAWAII
	1035							WASH OUT PUMP - LINES
	1040	1 1/2	0	✓		0		DISPLACE CEMENT
		1 1/2	6	✓		350		"
		1 1/2	10	✓		900		" HAWAII CEMENT CLEAR
		1	16	✓		1100		"
		1	17.3	✓		1300		" TUBING CLEAR
	1050	1	18	✓		1300		" SHUT DOWN
	1055	1/2	18 1/2	✓		800/1200		" "
	1100					800		SHUT IN - WASH TRUCK
	1120			✓		400/600		STAGE - BLEED OFF
	1130			✓		1000		" - HOLDING
	1135			✓		1500		" "
	1145					1500		RELEASE PSE - HELD
	1150	2 1/2	35		✓	400		RELEASE PKR - WASH 4 JTS DOWN THROUGH
	1230	3	30		✓	400		RW 2 JTS DOWN RATHOLE - REVERSE CUT PERFS
	1300			✓		200		PULL 9 JTS - PSE SQUEEZE - HELD - SHUT IN
	1400							JOB COMPLETE

THANK YOU  
WAYNE, FLEWY, KIRBY