



10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

TMMH
35

FIELD SERVICE TICKET
1718 18300 A

PRESSURE PUMPING & WIRELINE

DATE _____ TICKET NO. _____

DATE OF JOB 10-1-19 DISTRICT Pratt		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER TUTO Energy LLC		LEASE McClaren		WELL NO. 3				
ADDRESS		COUNTY KLONKA		STATE KS				
CITY STATE		SERVICE CREW MATTAI						
AUTHORIZED BY		JOB TYPE: 2-42 5 1/2" LONG STRING						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
19843	1						10-1	7:45
						ARRIVED AT JOB		10:10
						START OPERATION		1:57
19918	.5					FINISH OPERATION		3:00
						RELEASED		3:45
						MILES FROM STATION TO WELL		40

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
Bc 145	AA-2 Premium CRT	SK	265		7,155 00
cc 111	SALT	lb	1,084		542 00
cc 201	SILTSURFER	lb	1,303		1,303 00
cc 187	C-17	lb	123		2,952 00
cc 105	C-41P	lb	123		492 00
cc 151	MUD FLUSH	SAL	500		750 00
cc 6	DEPTH charge 5000' - 6000'	hr	1		2,900 00
me 101	Light well miles	mi	40		200 00
me 102	Heavy eq miles	mi	80		640 00
TM	ton miles	mi	492		1,476 00
ce 240	Blend + mix	SK	265		371 00
ce 504	Plug cost	EA	1		250 00
CF 1251	Auto fill float shoe	EA	1		360 00
ce 607	latch down plug + baffle	EA	1		400 00
ce 1651	TURBULEN	EA	10		1,100 00
Bc 143	SHARVISO	EA	1		75 00
Bc 144	DRIVER	EA	3		105 00

SUB TOTAL **21,071 00**

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		9,383 04

CHEMICAL / ACID DATA:			

SERVICE REPRESENTATIVE Mike Mattai	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: X/T.M
FIELD SERVICE ORDER NO.	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

Customer	TOTO Energy LLC	Lease No.		Date	10-1-19						
Lease	McClaren	Well #	3								
Field Order #	18700	Station	Pratt	Casing	5 1/2" RTO	Depth	5350	County	WYOMING	State	WY
Type Job	2-42 5 1/2" long string			Formation	120	5348	Legal Description	5-305-18w			

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size	5 1/2"	Tubing Size		Acid	215 AA-2	TOTO RATE	PRESS	ISIP
Depth	5325	From		Pre Pad	50 AA-2	Max TOTO Blend		5 Min.
Volume	123.8	From		Pad		Min		10 Min.
Max Press		From		Frac		Avg		15 Min.
Well Connection	Annulus Vol.	From				HHP Used		Annulus Pressure
Plug Depth	5281.25'	From		Flush	122.7	Gas Volume		Total Load

Customer Representative	Tim Myers	Station Manager	Westerman	Treater	MATTAI
Service Units	83353			19918	
Driver Names	MARAI				

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
10:10					ON LOCATION / SAFETY meeting
10:20					Run 5 1/2" casing 47# 43.75' shoe
					tubing 1, 3, 5, 7, 9, 11, 13, 15, 17, 19
12:41					Casing on bottom
12:52					Hook to casing / Break circ with rod
1:53	200		12	4	Pump 500 gal mud flush
1:57	210		5	5	Pump 5 bbl water
1:57	190		54	4.5	Mix 215 Sks AA-2
2:15			4	4	Wash Pump + Line / Drop Plug
2:19	100		-	6	START displacement
2:34	200		80	5.8	lift pressure
2:40	600		112	3	slow rate
2:42	800/1500		122.7		plug down / released + hold
2:50			7+5		plug rat + mouse hole
					circ. thru job
					JOB complete
					Thank You!
					Mike Mattai
					Edmund + Clarence