



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log


Customer:	Merit Energy	Cement Pump No.:	38750-19842	Operator TRK No.:	96815
Address:	sublette.invoices@meritenergy.com	Ticket #:	1718-19727 L	Bulk TRK No.:	19827-37725 33021-14284
City, State, Zip:	AFE- 64247	Job Type:	Z-42 Cement Surface Casing		
Service District:		Well Type:	OIL		
Well Name and No.:	Wright # 35-3	Well Location:	35-27S-33W	County:	Haskell State: Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
A CON BLEND	475	3%CaCl, 1/2#POLYFLAKE, 1#GILSONITE	19827-37725	Front	Back
C	165	2%CaCl, 1/4#POLYFLAKE	33021-14284	Front	Back
				Front	Back


Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel
Lead:	12.1	2.41	13.9	1144.75	Man Hours:
Tail:	14.8	1.34	6.33	221.1	# of Men on Job: 3

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
15:00							ON LOC, SAFTEY MTG, R.U.
19:32						1800	TEST LINES
7:37 PM	5.2					180	START LEAD @ 12.1#
8:16 PM	5	204				170	ON TAIL @ 14.8#
8:26 PM		39.5					SHUT DOWN, DROP PLUG
20:27	5					40	START DISPLACEMENT, WASHUP
20:49	2	95				600	SLOW RATE
8:54 PM		105.5				600-1100	PLUG DOWN
20:59							RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!
							<i>30 to 71</i>

Size Hole	12 1/4	Depth	1702'		TYPE	
Size & Wt. Csg.	8 5/8 24	Depth	1702.68'	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Top Plugs		Type			Perfs	CIBP

Customer Signature: 

Basic Representative: CHAD HINZ

Basic Signature: 

Date of Service: 8/27/2019

MERIT
WRIGHT 35-3

