

CUSTOMER *Downing + Nelson*

WELL NO. *1-24*

LEASE *Kramer Unit B*

JOB TYPE *PTA*

TICKET NO. *32598*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	<i>1900</i>							<i>On location, set up trucks, 1<sup>st</sup> Plug 50 SKS @ 3000' 2<sup>nd</sup> Plug 100 SKS @ 2050' 3<sup>rd</sup> Plug 50 SKS @ 525' Top off 8 5/8 w/ 10 SKS Rathole - 38 SKS Mouse hole - 15 SKS</i>
	<i>2000</i>	<i>4</i>	<i>10</i>					<i>1<sup>st</sup> Plug, 10 water, 13 Cement 3 1/2 water Big Pump Mud after for 3min Fin</i>
		<i>4</i>	<i>13</i>					
		<i>4</i>	<i>3 1/2</i>					
	<i>2015</i>							
	<i>2050</i>	<i>4</i>	<i>10</i>					<i>2<sup>nd</sup> Plug, 10 water, 26 Cement</i>
		<i>4</i>	<i>26</i>					
	<i>2100</i>	<i>4</i>	<i>6</i>					<i>6 water</i>
	<i>2150</i>	<i>4</i>	<i>5</i>					<i>3<sup>rd</sup> Plug, 5 water</i>
		<i>4</i>	<i>13</i>					<i>13 Cement</i>
	<i>2200</i>	<i>4</i>	<i>2</i>					<i>2 water</i>
	<i>2310</i>	<i>1</i>	<i>8</i>					<i>Plug Rathole</i>
		<i>1</i>	<i>4</i>					<i>Plug Mousehole</i>
	<i>2330</i>	<i>1</i>	<i>2 1/2</i>					<i>Top off 8 5/8"</i>
								<i>Washup Rackup</i>
								<i>Job Complete, Thanks Jon, Austin, Kirby</i>