

QUALITY WELL SERVICE, INC.

7213

Federal Tax I.D. # 481187368

Home Office 30060 N. Hwy 281, Pratt, KS 67124

Mailing Address P.O. Box 468

Office 620-727-3410

Fax 620-672-3663

Rich's Cell 620-727-3409

Brady's Cell 620-727-6964

Date	Sec.	Twp.	Range	County	State	On Location	Finish
8-30-19	7	30S	11W	Barber	Ks		
Lease	Dick Teust		Well No.	1-7			
Location		Isabel Ks W side 100 th rd					
Contractor			WW Dalg		Rig # 14		
Owner			1-7 S W IAD				
Type Job			Surface				
Hole Size			12 1/4		T.D. 236'		
Csg.			8 5/8 24'		Depth 236'		
Tbg. Size					Depth		
Tool					Depth		
Cement Left in Csg.			Shoe Joint 20		The above was done to satisfaction and supervision of owner agent or contractor.		
Meas Line			Displace 13.7		Cement Amount Ordered 21550 Common		
EQUIPMENT							
Pumptrk	8	No.		Common 21550			
Bulktrk	12	No.		Poz. Mix			
Bulktrk		No.		Gel. 409 #			
Pickup		No.		Calcium 606 #			
JOB SERVICES & REMARKS							
Rat Hole			Hulls				
Mouse Hole			Salt				
Centralizers			Flowseal 10.75"				
Baskets			Kol-Seal				
D/V or Port Collar			Mud CLR 48				
Run in 1/3 8 5/8 24" CSG set @ 236			CFL-117 or CD110 CAF 38				
START Csg on Bottom Hook up to CSG			Sand				
Break Circ w/ 12 1/4			Handling 231				
START Pumping 5 1/2" H2O			Mileage 25				
START Mix Pump 21050 Common			8 5/8 FLOAT EQUIPMENT				
2 1/2 GEL 3 1/2 CL 1/2" P.S @ 14.6 #/gal			Guide Shoe HEAD manifold				
SHUT DOWN Release 8 5/8 Wooden Plug			Centralizer 8 5/8 WOODEN PLUG 1 EA				
START also			Baskets				
Plug down			AFU Inserts				
Close Valve on CSG 150"			Float Shoe				
Good Circ thru JO3			Latch Down				
Circ CMT TO P.H			SERVICE SIGN 1 EA				
			LMV 25"				
			Pumptrk Charge Surface				
			Mileage 50				
			Tax				
			Discount				
			Total Charge				
Thank you PLEASE CALL AGAIN TODD TJ JAYC Signature <i>[Handwritten Signature]</i>							