

RECEIVED NOV 13 2019



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1002661	1718	11/04/2019
INVOICE NUMBER			
93081050			

Pratt (620) 672-1201
 B MC COY PETROLEUM CORP
 I PO Box: 39
 L SPIVEY
 L KS US 67142
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME Koehn F 1-29
 O LOCATION
 B COUNTY Haskell
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41194630	19919		Net - 30 days	12/04/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 11/03/2019 to 11/03/2019</i>				
0041194630				
171819812L Cement-New Well Casing/Pi 11/03/2019 Cement Surface Casing				
A-Serv Lite	625.00	SK		
Class C Cement	200.00	SK		
Celloflake	207.00	LB		
Calcium Chloride	2,008.00	LB		
Depth Charge, 1001'-2000'	1.00	HR		
Light Vehicle Mileage	40.00	MI		
Heavy Equipment Mileage	160.00	MI		
Ton Mileage	1,464.00	MI		
Blending & Mixing Service Charge	825.00	SK		
Plug Container Utilization Charge	1.00	EA		
Guide Shoe - Regular, 8 5/8" (Blue)	1.00	EA		
Flapper Type Insert Float Valves. 8 5/8"	1.00	EA		
Top Rubber Cement Plug, 8 5/8"	1.00	EA		
Centralizer, 8 5/8" (Blue)	4.00	EA		
Service Supervisor Charge	1.00	EA		
Driver Charge	3.00	EA		
Sugar	50.00	LB		

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOT:	0
BASIC ENERGY SERVICES,LP	BASIC ENERGY SERVICES,LP		8
PO BOX 841903	801 CHERRY ST, STE 2100		8
DALLAS, TX 75284-1903	FORT WORTH, TX 76102	INVOICE TOT:	8



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	McCoy Petroleum Corporation	Cement Pump No.:	38117 19919 HRS	Operator TRK No.:	96816	
Address:	9342 E. Cemtral	Ticket #:	1718 19813 L	Bulk TRK No.:	37712 19883 Victor	19827 37725 Corey
City, State, Zip:	Wichita, Kansas 67206	Job Type:	Z-42 Cement Surface Casing			
Service District:	1718-Liberal KS	Well Type:	NEW			
Well Name and No.:	Koehn "F" # 1-29	Well Location:	29-29S-31W	County:	Haskell	State: Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
A Serv Lite	625	3% calcium chloride, +.25pps Celloflake	37712 19883 Victor	Front	Back
Class C Cement	200	2% Calcium chloride, +.25pps Celloflake	19827 37725 Corey	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	12.3	2.08	11.52	1300	TT Man Hours:	28
Tail:	14.8	1.34	6.33	268	# of Men on Job:	4

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
0830							ON LOCATION -- SPOT AND RIG UP
1310							CASING ON BOTTOM -- BREAK CIRC
1315							SAFETY MEETING
1330					1500		PRESSURE TEST
1336	4	10			250		PUMP FRESH WATER SPACER
1339	5	232			200		MIX LEAD CEMENT @ 12.3 PPG
1423	5	48			100		MIX TAIL CEMENT @ 14.8 PPG
1434							SHUT DOWN -- DROP TOP PLUG
1437	5	0			100		START DISPLACEMENT
1457	1	94			450		SLOW RATE
1523		113.7			600-1100		BUMP PLUG
1537					800		FLOAT DID NOT HOLD -- SHUT IN HEAD
		50					CIRCULATE CEMENT TO THE PIT

Size Hole	12 1/4	Depth	1836		TYPE	
Size & Wt. Csg.	8.625 24#	Depth	1830.99	New / Used	NEW	Packer
tbg.		Depth	42.2	SHOE		Retainer
Top Plugs		Type				Perfs

Customer Signature: <i>Alm Lipton</i>	Basic Representative:	Kirby Harper
	Basic Signature:	
	Date of Service:	11/3/2019