



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1002750	1718	09/27/2019
INVOICE NUMBER			
93056387			

Pratt (620) 672-1201  
 B MIDWESTERN EXPLORATION CO.  
 I \*\*\*3500 S. BOULEVARD STE 2B\*\*  
 L EDMOND  
 L OK US 73013  
 T  
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME TONY NIX 4-6  
 O LOCATION  
 B COUNTY STEVENS  
 S STATE KS  
 I JOB DESCRIPTION Cement-New Well Casing/Pi  
 T JOB CONTACT  
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41191228	19572		Net - 30 days	10/27/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 09/26/2019 to 09/26/2019</i>				
0041191228				
171819696L Cement-New Well Casing/Pi 09/26/2019 CEMENT PRODUCTION CASING				
AA2 Premium Cement	325.00	SK	7.98	2,593.50 T
Gypsum	1,530.00	LB	0.45	688.50 T
1803 LBS Salt	1.00	LB	414.69	414.69 T
Gilsonite	1,625.00	LB	0.45	731.25 T
C-17	153.00	LB	10.80	1,652.40 T
C-41P	77.00	LB	1.80	138.60 T
Auto Fill Float Shoe 5 1/2" (Blue)	1.00	EA	360.00	360.00
Latch Down Plug & Baffle, 5 1/2" (Blue)	1.00	EA	400.00	400.00
Turbolizer, 5 1/2" (Blue)	12.00	EA	110.00	1,320.00
Heavy Equipment Mileage	40.00	MI	3.60	144.00
Blending & Mixing Service Charge	325.00	SK	0.63	204.75
Ton Mileage	306.00	MI	1.35	413.10
Depth Charge, 6001'-7000'	1.00	HR	1,485.00	1,485.00
Plug Container Utilization Charge	1.00	EA	112.50	112.50
Light Vehicle Mileage	20.00	MI	2.25	45.00
Cement Densimeter, with chart recorder	1.00	EA	157.50	157.50
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	3.00	EA	35.00	105.00
500 GALS Mud Flush	1.00	GAL	340.00	340.00 T

POSTED

MIDWESTERN EXPLORATION COMPANY  
 LEASE Jonitrol RECEIVED OCT 03 2019  
 ORLG (D) TANG. INTANG.  
 COMP. TANG. INTANG.  
 OP. EXP. 71290 USED FOR: Cement & Services - Surf

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	11,380.79
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	491.92
PO BOX 841903	CORRY ST, STE 2100	INVOICE TOTAL	11,872.71
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		
APPROVED BY: _____	DATE PAID: _____		







Liberal Yard #1717 none 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

**PRESSURE PUMPING Job Log**

Customer:	Midwestern Exploration Company	Cement Pump No.:	37223 19572 15HRS	Operator TRK No.:	78868	
Address:	3500 S Boulevard STE 2B	Ticket #:	1718 19696 L	Bulk TRK No.:	37712 19883 Sam	37712 19883
City, State, Zip:	Edmond Ok 73013	Job Type:	Z-42 Cement Production Casing			
Service District:	1718-Liberal KS	Well Type:	OIL			
Well Name and No.:	Tony Nix # 4-6	Well Location:	6-35S-35W	County:	Stevens	State: Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
AA-2 Premium Cement	325	10% Gypsum, 10% Salt, 5# Gilsonite, .5% C-17, 1/4# Defoamer	37712 19883 Sam	Front	Back
			37712 19883	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
<b>Lead:</b>	14.8	1.51	6.65	490.75	TT Man Hours:	48
<b>Tail:</b>					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
14:00pm							Arrived at location
18:00pm							Spot trucks/Rig up
20:45pm						2000	Safety meeting/Pressure test lines to 2000psi
21:17pm	2	13.4				20	Pump 13.4bbls of cement from 50sks at 14.8lbs to fill rat and mouse hole
21:35pm	4	11.9				350	Pump 11.9bbls of mud flush spacer
21:39pm	4	73.9				170	Pump 73.9bbls of cement from 275sks at 14.8lbs
22:05pm							Shut down/Drop plug/Wash pump and lines to pit
22:17pm							Start displacement of bbls with fresh water
22:19pm	8	20				300	20bbls gone
22:22pm	8	40				300	40bbls gone
22:24pm	8	60				300	60bbls gone
22:26pm	8	80				300	80bbls gone
22:29pm	8	100				350	100bbls gone
22:32pm	7	120				600	120bbls gone
22:35pm	6	140				820	140bbls gone
22:37pm	6	148				820	148bbls gone/Slow down rate
22:41pm	2	158				1820	Bump plug/Hold for 2 minutes
22:23pm							Release pressure to check if float holds
							Rig down
							Job completed
							Thanked company man and rig crew

Size Hole	7 7/8	Depth	6670		TYPE	Baffle	
Size & Wt. Csg.	5 1/2 15.5#	Depth	6677.49	New / Used	Baffle	6639.39	Depth
Landing Psi	1000+	Depth			Retainer		Depth
Shoe Joint	38.1	Type			Peris		CIBP

Customer Signature: *Billy Daugherty*

Basic Representative: Victor A. Corona

Basic Signature: *Victor A. Corona*

Date of Service: 9/26/2019

**Midwestern Exploration  
 Tony Nix 4-6  
 5 1/2 Production  
 9/26/2019**

