



WF (C) Tony V
 Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Berexco LLC	Cement Pump No.:	37223 19572 14HRS	Operator TRK No.:	86531
Address:	2020 N. Bramblewood	Ticket #:	1718 19786 L	Bulk TRK No.:	27808 19578 Corey
City, State, Zip:	Wichita, Kansas 67206-1094	Job Type:	Z-42 Cement Surface Casing		
Service District:	1718-Liberal Ks	Well Type:			
Well Name and No.:	MRM #2	Well Location:	15 - 10S - 33W	County:	Thomas
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
Class C Cement	300	3% Calcium Chloride, +.25pps Cello-Flake	27808 19578 Corey	Front	Back
			27808 19578	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	14.8	1.35	6.35	405	TT Man Hours	46
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
12:30pm							Arrived at location
12:45pm							Spot trucks/Rig up
16:00pm							Safety meeting
16:40pm	2	5			80		Pump 5 bbls of fresh water spacer
16:43pm	5	72			200		Pump 72bbls of cement from 300sks at 14.8lbs
							Shut down/Wash pump and lines
17:0pm							Start displacement with fresh water
17:04pm	4.3	10					10bbls gone
17:06pm	5	20					20bbls gone
17:09pm	3	22					Bump plug/Close valve on swedge
							Got 30bbls of cement to surface
							Rig down
							Job completed
							Thanked company man and rig crew

Size Hole	12 1/4	Depth	394		TYPE	Float Shoe	
Size & Wt. Csg.	8 5/8 24#	Depth	390.65	New / Used	Float Shoe	348.46	Depth
Landing Psi	500+	Depth			Retainer		Depth
Shoe Joint	42.19	Type			Perfs		CIBP

Customer Signature:	Basic Representative:	Victor A. Corona
	Basic Signature:	<i>Victor A. Corona</i>
	Date of Service:	10/23/2019