

1718 18500 A

**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61  
P.O. Box 8613  
Pratt, Kansas 67124  
Phone 620-672-1201

TMH 30

DATE \_\_\_\_\_ TICKET NO. 18500

DATE OF JOB 11-22-19 DISTRICT Pratt, KS #1718 NEW WELL  OLD WELL  PROD  INJ  WDW  CUSTOMER ORDER NO.: \_\_\_\_\_

CUSTOMER Grunder Oil LEASE Leesborg Grunder WELL NO. 3

ADDRESS \_\_\_\_\_ COUNTY Stafford STATE Kansas

CITY \_\_\_\_\_ STATE \_\_\_\_\_ SERVICE CREW Carl B Ron G Jose D

AUTHORIZED BY \_\_\_\_\_ JOB TYPE: 8<sup>th</sup> surface Z-42

EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
<u>27463</u>	<u>-5</u>						<u>11-22-19</u>			
<u>9903-9862</u>	<u>-50</u>									
						ARRIVED AT JOB				<u>7:30</u>
						START OPERATION				<u>9:30</u>
						FINISH OPERATION				<u>10:15</u>
						RELEASED				<u>11:00</u>
						MILES FROM STATION TO WELL				<u>20</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: Chf Maghuel  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

EM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
<u>2C118</u>	<u>A-con Blend</u>	<u>SX</u>	<u>175</u>		<u>8750</u>
<u>2C132</u>	<u>60:40: P02</u>	<u>SX</u>	<u>175</u>		<u>4725</u>
<u>2C102</u>	<u>Cellulose Flake</u>	<u>lb</u>	<u>352</u>		<u>352</u>
<u>2C109</u>	<u>Calcium chloride</u>	<u>lb</u>	<u>948</u>		<u>948</u>
<u>ME101</u>	<u>Light Vehicle Mileage</u>	<u>Mi</u>	<u>20</u>		<u>100</u>
<u>ME102</u>	<u>Heavy equipment Mileage</u>	<u>Mi</u>	<u>40</u>		<u>320</u>
<u>E504</u>	<u>Plug container utilization charge</u>	<u>ea</u>	<u>1</u>		<u>250</u>
<u>C1</u>	<u>Depth charge 0-1000'</u>	<u>HQ</u>	<u>1</u>		<u>1200</u>
<u>E240</u>	<u>Blending + mixing charge</u>	<u>SX</u>	<u>350</u>		<u>490</u>
<u>F105</u>	<u>Top Rubber plug</u>	<u>ea</u>	<u>1</u>		<u>225</u>
<u>F753</u>	<u>Baffle plate</u>	<u>ea</u>	<u>1</u>		<u>170</u>
<u>E143</u>	<u>Service Supervisor Charge</u>	<u>ea</u>	<u>1</u>		<u>75</u>
<u>E144</u>	<u>Driver Charge</u>	<u>ea</u>	<u>3</u>		<u>105</u>

SUB TOTAL 17,710

CHEMICAL / ACID DATA:


SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$

TOTAL 6315 50

SERVICE REPRESENTATIVE Carl Beldy THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: Chf Maghuel  
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO. \_\_\_\_\_

Customer: <b>Grunder Oil</b>	Lease No.:	Date: <b>11-22-19</b>
Lease: <b>Leesburg</b>	Well #: <b>3</b>	
Field Order #: <b>18500</b>	Station: <b>Pratt KS.</b>	Casing: <b>8 5/8</b>
Type Job: <b>8 5/8 surface</b>	Formation:	Depth: <b>644'</b>
		County: <b>Stafford</b>
		State: <b>KS.</b>
		Legal Description: <b>14-255-13w</b>

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size: <b>8 5/8</b>	Tubing Size:	Shots/Ft:		Acid	RATE	PRESS	ISIP
Depth: <b>644'</b>	Depth:	From:	To:	Pre Pad	Max		5 Min.
Volume: <b>38.38</b>	Volume:	From:	To:	Pad	Min		10 Min.
Max Press: <b>500</b>	Max Press:	From:	To:	Frac	Avg		15 Min.
Well Connection: <b>U+M</b>	Annulus Vol.:	From:	To:		HHP Used		Annulus Pressure
Plug Depth: <b>604'</b>	Packer Depth:	From:	To:	Flush	Gas Volume		Total Load

Customer Representative:	Station Manager: <b>Justin Westerman</b>	Treater: <b>Casey Aldridge</b>
Service Units: <b>27463 19903 19862</b>		
Driver Names: <b>Ron G Tocz Dias</b>		

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
7:30 AM					on location + Rig up
9:15 AM					Ran 644' 8 5/8 casing Break circulation with Rig Rig up to Cement
9:30 AM	150		3	3	Start Freshwater
	150		77	5	Start Acow Blend 1TS SX
	150		37	5	Start 80:40:702 Tail 1TS SX
10:00 AM					Cement in stop pumps Release plug
10:05 AM				4.5	Start Displacement
	50			4.5	steady rate
	300		35	2.5	slow rate @ 35 Bbls out
10:15 AM	500		3.5	2.5	Bump plug 33.5 Bbls water shut in
	300				
					Cement did circulate
					Thank you



Customer <b>BRUNDER OIL</b>		Lease No.		Date <b>12/1/19</b>	
Lease <b>BRUNDER</b>		Well # <b>3</b>			
Field Order #	Station <b>FRATT</b>	Casing	Depth	County <b>STAFFORD</b>	State <b>KS</b>
Type Job <b>PLUG TO ABANDON</b>			Formation <b>ARBUCKLE</b>	Legal Description	

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP
Depth	Depth	From	To	Pre Pad	Max		5 Min.
Volume	Volume	From	To	Pad	Min		10 Min.
Max Press	Max Press	From	To	Frac	Avg		15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth	Packer Depth	From	To	Flush	Gas Volume		Total Load

Customer Representative <b>C. MAYFIELD</b>	Station Manager <b>JUSTIN W.</b>	Treater <b>KEVIN BRUNGARDT</b>
--	----------------------------------	--------------------------------

Service Units	<b>19843</b>	<b>70959</b>	<b>19860</b>	<b>98620</b>				
Driver Names	<b>MIKE MATAL</b>	<b>JESSE HANKE</b>	<b>KEVIN</b>					

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<b>8:15</b>					<b>ON LOCATION - SPOT EQUIPMENTS JOB + SAFETY</b>
<b>9:45</b>	<b>500</b>				<b>4253' - 50 SKS - START H2O</b>
			<b>8 1/2</b>	<b>4</b>	<b>H2O IN - START CEMENT</b>
			<b>12 3/4</b>	<b>4</b>	<b>CEMENT IN - START H2O</b>
			<b>3</b>	<b>4</b>	<b>H2O IN - STOP PUMP</b>
			<b>54</b>		<b>DISPLACE DRILL PIPE WITH RTG PUMP @ TOOLPUSHERS REQUEST</b>
	<b>250</b>			<b>4</b>	<b>700 - 80 SKS - START H2O</b>
			<b>8 1/2</b>	<b>4</b>	<b>H2O IN - START CEMENT</b>
			<b>20</b>	<b>3</b>	<b>CEMENT IN - START H2O</b>
			<b>4</b>	<b>3</b>	<b>H2O IN - STOP PUMP</b>
	<b>100</b>			<b>3</b>	<b>60' - 20 SKS - LOAD HOPE</b>
			<b>5</b>	<b>3</b>	<b>CIRCULATE CEMENT</b>
	<b>100</b>		<b>7 1/2</b>	<b>2</b>	<b>RATHOLE - 30 SKS</b>
<b>3:00</b>	<b>100</b>		<b>5</b>	<b>2</b>	<b>MOUSEHOLE - 20 SKS</b>