

Jones Exploration  
well 30

Ackarman Inc  
Ackarman Hardware & Lumber  
160 East Main St  
Sedan KS 67361  
620-725-3103

10/8/2019 1:26 PM

BRCH:1000 \*\*\* INVOICE \*\*\*  
CASHIER: BL 1910-152035  
SLSP:CM

ACCT # : CASH  
JOB # : 0  
NAME : CASH SALES

MP10092 PORTLAND CEMENT 92.6#

8 EACH @ 16.75EACH 134.00

SUBTOTAL 134.00  
SALES TAX KS 10.00% 13.40

TOTAL 147.40  
AMT PAID 147.40  
CHANGE DUE 0.00

PAYMENT METHOD[S]:

SALE-MasterCard 147.40  
ACCT:###8941 APPROVED:69297H  
AL: MasterCard  
Entry Mode: CHIP  
AID: A0000000041010

Jones Exploration  
well 26

Ackarman Inc  
Ackarman Hardware & Lumber  
160 East Main St  
Sedan KS 67361  
620-725-3103

9/17/2019 8:05 AM

BRCH:1000 \*\*\* INVOICE \*\*\*  
CASHIER: BL 1909-150684  
SLSP:CM

ACCT # : CASH  
JOB # : 0  
NAME : CASH SALES

MP10092 PORTLAND CEMENT 92.6#

10 EACH @ 16.75EACH 167.50  
~~3910361 SILVER GORILLA TAPE 35YD~~

1 EA @ 13.99 EA 13.99

SUBTOTAL 181.49  
SALES TAX KS 10.00% 16.75

TOTAL 199.64  
AMT PAID 184.25  
CHANGE DUE 0.00

PAYMENT METHOD[S]:

SALE-MasterCard 199.64  
ACCT:###8941 APPROVED:69330H  
AL: MasterCard  
Entry Mode: CHIP  
AID: A0000000041010



**HURRICANE SERVICES INC**

Customer: <b>Jones Oil Exploration</b>	Lease & Well #: <b>Butcher #30</b>	Date: <b>15-Oct</b>
Service District: <b>Bartlesville</b>	County & State: <b>CQ, Kansas</b>	Job #: <b>ICT2580</b>
Job Type: <b>Long String</b>	Legals S/T/R: <b>25 33s 10E</b>	Ticket #: <b>ICT2580</b>
<input checked="" type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> SWD <input type="checkbox"/> YES <input checked="" type="checkbox"/> No	<b>Job Safety Analysis - A Discussion of Hazards &amp; Safety Procedures</b> <input checked="" type="checkbox"/> Hard hat <input checked="" type="checkbox"/> Gloves <input type="checkbox"/> Lockout/Tagout <input checked="" type="checkbox"/> Warning Signs & Flagging <input checked="" type="checkbox"/> H2S Monitor <input checked="" type="checkbox"/> Eye Protection <input type="checkbox"/> Required Permits <input checked="" type="checkbox"/> Fall Protection <input checked="" type="checkbox"/> Safety Footwear <input type="checkbox"/> Respiratory Protection <input type="checkbox"/> Slip/Trip/Fall Hazards <input type="checkbox"/> Specific Job Sequence/Expectations <input type="checkbox"/> FRC/Protective Clothing <input type="checkbox"/> Additional Chemical/Acid PPE <input type="checkbox"/> Overhead Hazards <input type="checkbox"/> Muster Point/Medical Locations <input checked="" type="checkbox"/> Hearing Protection <input type="checkbox"/> Fire Extinguisher <input type="checkbox"/> Additional concerns or issues noted below	
Equipment #	Driver	
94	John Wade	
212	Kevin	
219	Corbin	
199/127	Ben	
<b>Comments</b>		

Product Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Rem Discount	Net Amount
M015	Light Equipment Mileage	mi	70.00	\$2.00	\$140.00	32%	\$95.20
M010	Heavy Equipment Mileage	mi	70.00	\$4.00	\$280.00	32%	\$190.40
M020	Ton Mileage	tm	475.00	\$1.50	\$712.50	32%	\$484.50
C010	Cement Pump	ea	1.00	\$750.00	\$750.00	32%	\$510.00
C050	Cement Plug Container	job	1.00	\$375.00	\$375.00	32%	\$255.00
CP010	Class A Cement	sack	140.00	\$17.00	\$2,380.00	32%	\$1,618.40
CP095	Bentonite Gel	lb	750.00	\$0.30	\$225.00	32%	\$153.00
CP110	Kol Seal	lb	700.00	\$0.75	\$525.00	32%	\$357.00
CP125	Pheno Seal	lb	80.00	\$1.75	\$140.00	32%	\$95.20
CP140	Salt	sack	18.00	\$10.00	\$180.00	32%	\$122.40
AF080	Fresh Water	gal	5,460.00	\$0.02	\$81.90	32%	\$55.69
FE115	4 1/2" Rubber Plug	ea	1.00	\$75.00	\$75.00	32%	\$51.00
T030	Transport - 130 bbl	hr	6.00	\$130.00	\$780.00	32%	\$530.40
					<b>Gross:</b>		<b>\$4,518.19</b>

Customer Section: On the following scale how would you rate Hurricane Services Inc?

Based on this job, how likely is it you would recommend HSI to a colleague?

1     2     3     4     5     6     7     8     9     10    Extremly Likely

<b>Total Taxable</b> \$ -	<b>Tax Rate:</b>	<b>Net:</b> \$4,518.19
State tax laws deem certain products and services used on new wells to be sales tax exempt. Hurricane Services relies on the customer provided well information above to make a determination if services and/or products are tax exempt.		<b>Sale Tax:</b> \$ -
		<b>Total:</b> \$ 4,518.19

HSI Representative: *[Signature]*

**TERMS:** Cash in advance unless Hurricane Services Inc. (HSI) has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts shall pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws. In the event it is necessary to employ an agency and/or attorney to affect the collection, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount is immediately due and subject to collection. Prices quoted are estimates only and are good for 30 days from the date of issue. Pricing does not include federal, state, or local taxes, or royalties and stated price adjustments. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services. Any discount is based on 30 days net payment terms or cash. **DISCLAIMER NOTICE:** Technical data is presented in good faith, but no warranty is stated or implied. HSI assumes no liability for advice or recommendations made concerning the results from the use of any product or service. The information presented is a best estimate of the actual results that may be achieved and should be used for comparison purposes and HSI makes no guarantee of future production performance. Customer represents and warrants that well and all associated equipment in acceptable condition to receive services by HSI. Likewise, the customer guarantees proper operational care of all customer owned equipment and property while HSI is on location performing services. The authorization below acknowledges the receipt and acceptance of all terms/conditions stated above, and Hurricane has been provided accurate well information in determining taxable services.

X *[Signature]* **CUSTOMER AUTHORIZATION SIGNATURE**



**CEMENT TREATMENT REPORT**

Customer: <b>Jones Oil Exploration</b>	Well: <b>Butcher #E #30</b>	Ticket: <b>ICT2580</b>
City, State:	County: <b>CQ, Kansas</b>	Date: <b>10/15/2019</b>
Field Rep: <b>Matt Jones</b>	S-T-R: <b>25 33s 10E</b>	Service: <b>Long String</b>

Downhole Information	
Hole Size:	<b>6 3/4 in</b>
Hole Depth:	<b>ft</b>
Casing Size:	<b>4 1/2 in</b>
Casing Depth:	<b>ft</b>
Tubing / Liner:	<b>in</b>
Depth:	<b>ft</b>
Tool / Packer:	
Depth:	<b>ft</b>
Displacement:	<b>bbbls</b>

Calculated Slurry	
Weight:	<b>14.1 # / sx</b>
Water / Sx:	<b>8.10 gal / sx</b>
Yield:	<b>1.68 ft<sup>3</sup> / sx</b>
Bbls / Ft.:	
Depth:	<b>ft</b>
Annular Volume:	<b>0 bbls</b>
Excess:	
Total Slurry:	<b>42.0 bbls</b>
Total Sacks:	<b>140 sx</b>

Product	% / #	#
Class A	<b>100.00</b>	
Poz		
Gel	<b>4.00</b>	<b>0</b>
CaCl		
Gypsum		
Metso		
Kol Seal	<b>5.00</b>	<b>0</b>
Phenoseal	<b>0.40</b>	<b>0</b>
Salt (bww)	<b>10.00</b>	<b>0</b>
<b>Total</b>		<b>-</b>

TIME	RATE	PSI	BBLs	REMARKS
				Class a 4% gel, 10% salt, 5# kolseal, .1# phenoseal 14.1ppg 8.1 water 1.68 yield
				Hooked up to well and established circulation pumping 5bbl water ahead of a 200# gel sweep. Ran 140sks cement at 14.1ppg. Shut down and washed pump and lines. Dropped plug and displaced 21.7bbl to land plug at 1000psi.
				Plug did not hold. Landed plug again at 1200psi and plug held. Topped off well and washed up pump truck
				Circulated 6bbl cement to pit. Thank You
1:00pm				On Location
1:05pm				JSA
1:10 AM				Hooked up to well
1:15 AM			15.0	Establish circulation pumping 5bbl water ahead of 200# gel sweep.
1:20 PM		200.0	41.0	Ran 140sks cement
1:35pm			5.0	Dropped plug and washed pump and lines
1:37 AM		500.0	21.7	Displaced plug
1:50pm				Landed plug
		1,200.0		Washed up pump truck.

CREW			UNIT	SUMMARY		
Cementer:	<b>John Wade</b>		<b>94</b>	Average Rate	Average Pressure	Total Fluid
Pump Operator:	<b>Kevin</b>		<b>212</b>	#DIV/0! bpm	633 psi	83 bbls
Bulk #1:	<b>Corbin</b>		<b>219</b>			
Bulk #2:	<b>Ben</b>		<b>199/127</b>			

Hurricane Services, Inc.  
 250 N. Water  
 Wichita, KS 67202