


810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **4801**
Foreman Kevin McCoy
Camp EUREKA

Date	Cust. ID #	Lease & Well Number		Section	Township	Range	County	State
11-8-19	1215	D. wiebe #32-1		32	235	5E	Butler	Ks
Customer				Unit #	Driver	Unit #	Driver	
ENTRANSCO ENERGY, LLC				104	ALAN M.			
Mailing Address				113	JASON H.			
P.O. Box 578				141	JOSH V.			
City								
Dewey		State	Zip Code					
		OK	74029					

Job Type Longstring Hole Depth 2615' K.B. Slurry Vol. 49 BBL Production CASING Tubing _____
 Casing Depth 2600.42' G.L. Hole Size 7 7/8" Slurry Wt. 13.8* Drill Pipe _____
 Casing Size & Wt. 5 5/2 15.50* Cement Left in Casing 0' Water Gal/SK 9.0 Other _____
 Displacement 64 BBL Displacement PSI 1000 Bump Plug to 1500 PSI BPM _____

Remarks: Safety Meeting: Rig up to 5 1/2 casing w/ rotating swivel & head. BREAK circulation w/ 15 BBL fresh water. Mixed 150 SKS THICK SET Cement w/ 5" Kol-Seal/SK, 1" PhenoSeal/SK @ 13.8*/gal, yield 1.85 = 49 BBL Slurry = 277 ft³. Wash out Pump & Lines. Shut down, Release Latch down Plug. Displace Plug to seat w/ 64.0 BBL fresh water (KCL in first 40 BBL) Final Pumping Pressure 1600 PSI. Bump Plug to 1500 PSI. Wait 2 mins. Release Pressure. Float & Plug Held. Rotated casing while displacing Plug. Job Complete. Rig down.

Note: Plug R.H. w/ 20 SKS, M.H. w/ 15 SKS

CENTRALIZERS ON #1, 5, 9, 12, 15

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge		
C 107	40	Mileage	1100.00	1100.00
			4.20	168.00
C 201	185 SKS	THICK SET Cement	20.50	3792.50
C 207	925 #	KOL-SEAL 5"/SK	.47*	434.75
C 208	185 #	PHENOSEAL 1"/SK	1.30*	240.50
C 108.B	10.18 TONS	TON Mileage 40 miles	1.40	570.08
C 113	4 HRS	80 BBL VAC TRUCK	90.00	360.00
C 224	3300 GALS	CITY WATER	10.00/1000	33.00
C 222	5 GAL	KCL	30.00	150.00
C 421	1	5 1/2 LATCH DOWN PLUG	242.00	242.00
C 661	1	5 1/2 AFU FLOAT SHOE	309.00	309.00
C 504	5	5 1/2 x 7 7/8 CENTRALIZERS	50.00	250.00
C 112	1	5 1/2 ROTATING SWIVEL RENTAL	105.00	105.00
			Sub Total	7754.80
			Less 5%	405.80
			Sales Tax	361.19
			6.5%	
Authorization _____ Title _____			Total	7710.19

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.