

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. **4803**

Foreman Kevin McCoy

Camp EUREKA

ADT # 15-015-24133

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
11-13-19	1215	D. Wiebe # 32-3	32	25S	5E	Butler	Ks	
Customer			Safety Meeting	Unit #	Driver	Unit #	Driver	
ENTRANSKO ENERGY, LLC			KM AM 2A	104	ALAN M.			
Mailing Address				110	Zevi A.			
P.O. Box 578								
City	State	Zip Code						
Dewey	OK	74029						

Job Type SURFACE Hole Depth 223 K.B. Slurry Vol. 32 BBL Tubing _____
 Casing Depth 210' G.L. Hole Size 12 1/4" Slurry Wt. 15# Drill Pipe _____
 Casing Size & Wt. 8 5/8 23# Cement Left in Casing 15' Water Gal/SK _____ Other _____
 Displacement 13 BBL Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 8 5/8 casing. BREAK CIRCULATION w/ 10 BBL FRESH WATER. Mixed 135 SKS CLASS A Cement w/ 3% CaCl2, 2% Gel, 1/4" FloSeal/sk @ 15#/gal = BBL Slurry. Displace w/ 13 BBL Fresh water. Shut casing in. Good Cement Returns to Surface = 5 BBL Slurry to Pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 101	1	Pump Charge	890.00	890.00
C 107	40	Mileage	4.20	168.00
C 200	135 SKS	CLASS A Cement	15.75	2126.25
C 205	380 #	CaCl2 3%	.63 #	239.40
C 206	250 #	Gel 2%	.21 #	52.50
C 209	34 #	FloSeal 1/4 #/sk	2.35 #	79.90
C108A	6.35 TONS	Ton Mileage	M/C	365.00
			Sub Total	3921.05
			Less 5%	204.17
			Sales Tax	162.37
			Total	3879.25

THANK YOU
 M

Authorization _____ Title _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4782**
 Foreman David Gardner
 Camp Eureka

API # 15-015-24133

Date	Cust. ID #	Lease & Well Number		Section	Township	Range	County	State
11-16-19	1215	D. Wiebe #32-3		32	23 S.	5 E.	Butler	KS
Customer			Safety Meeting DG AM KM ZM	Unit #	Driver	Unit #	Driver	
Mailing Address				104	Alan			
City				112	Kevin			
State				145	Zevi			
City		State	Zip Code					
Dewey		OK	74029					

Job Type Longstring Hole Depth 2610' K.B. Slurry Vol. 49 Bbl Production casing Tubing _____
 Casing Depth 2594.20' G.L. Hole Size 7 7/8" Slurry Wt. 13.8# Drill Pipe _____
 Casing Size & Wt. 5 1/2" 15.50# Cement Left in Casing 0' Water Gal/SK 9.0 Other _____
 Displacement 64 Bbl Displacement PSI 1000 Bump Plug to 1500 PSI BPM _____

Remarks: Safety Meeting. Rig up to 5 1/2" casing w/ Rotating Swivel + Head. Break circulation w/ 15 Bbl fresh water. Mixed 150 sks Thick Set Cement w/ 5" Kolseal/sk, 1" Phenoseal/sk @ 13.8#/gal, yield 1.85 = 49 Bbl Slurry = 277 Ft³. Wash out pump + lines. Shut down. Release Latch Down plug. Displace plug to seat w/ 64 Bbl fresh water. (KCL in 1st 40 Bbl). Final pumping pressure of 1000 PSI. Bump plug to 1500 PSI. Wait 2 mins. Release pressure. float + Plug held. Rotated casing while displacing plug. Job Complete. Rig down.

Note: Plug R.H. w/ 20 sks, M.H. w/ 15 sks

Centralizers on #1, 5, 9, 12, 15

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	1100.00	1100.00
C107	40	Mileage	4.20	168.00
C201	185 sks	Thick Set Cement	20.50	3,792.50
C207	925#	Kolseal @ 5#/sk	.47	434.75
C208	185#	Phenoseal @ 1#/sk	1.30	240.50
C108B	10.18 Trns	Trn Mileage - Bulk Truck	1.40	570.08
C113	4 HRS	80 Bbl Vac Truck	90.00	360.00
C224	3300 Gals	City Water	10.00/1000	33.00
C222	5 Gals	KCL	30.00	150.00
C421	1	5 1/2 Latch Down Plug	242.00	242.00
C661	1	5 1/2 AFU Float Shoe	309.00	309.00
C504	5	5 1/2 x 7 3/8 Centralizers	50.00	250.00
C112	1	5 1/2 Rotating Swivel Rental	105.00	105.00
			Sub Total	7,754.83
			Less 5%	405.80
			Sales Tax	361.19
			6.5%	
Authorization <u>[Signature]</u> Title _____			Total	7,710.22

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.