

JOB LOG

SWIFT Services, Inc.

DATE 10/16/19 PAGE NO. 1

CUSTOMER Blue Ridge Petroleum		WELL NO. 1-30		LEASE Schlegel - French		JOB TYPE Surface		TICKET NO. 032425	
----------------------------------	--	------------------	--	----------------------------	--	---------------------	--	----------------------	--

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	

	0800							On location 8 5/8" 24 lb/ft
--	------	--	--	--	--	--	--	-----------------------------

								RTD = 677
--	--	--	--	--	--	--	--	-----------

	0800							Start 8 5/8" Casing in well
--	------	--	--	--	--	--	--	-----------------------------

	0930							Break Circulation
--	------	--	--	--	--	--	--	-------------------

	0945	4	10		✓		200	Pump 10 bbl KCL H2O Spacer
--	------	---	----	--	---	--	-----	----------------------------

	0950	4	81		✓		250	Mix 335 sks of Standard 2% gel 3% CC 1/4" Flo @ 14.7 ppg
--	------	---	----	--	---	--	-----	---

	1020	4	0		✓		250	Start Displacement
--	------	---	---	--	---	--	-----	--------------------

		4	35		✓		300	- Circulate CMT to Surface - 25 sks to the Pit
--	--	---	----	--	---	--	-----	---

	1040		35 42		✓ ✓			KO Pump - Plug Down Release Pressure * Value Hold *
--	------	--	---------------------	--	-------------------	--	--	--

	1045							Wash up Trk # 112
--	------	--	--	--	--	--	--	-------------------

	1100							Job Complete
--	------	--	--	--	--	--	--	--------------

335 sks of Standard 2% gel 3% CC
1/4" Floccle used - Plug down @ 10:40 AM

Thank You,

Budeon, Preston, Isaac