

JOB LOG

SWIFT Services, Inc.

DATE 10-25-19 PAGE NO. 1

CUSTOMER Blue Ridge Petroleum WELL NO. 1-30 LEASE Schlegel-French JOB TYPE Long String 5 1/2" TICKET NO. 032858

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0030							On Location 5 1/2" @ 15.5 lb/ft
								RTD: 4,655' PC: 1885' #6 SJ: 43.21 Turbo: 1, 2, 3, 4, 5, 6, 7, 67 Baskets: 65, 66
	0200 0415							Start 5 1/2" 23 lb/ft Casing in well Drop Ball - Circulate
	0515	6 1/2	12		✓			Pump 500 gal Mud Flush
		6 1/2	20		✓			Pump 20 bbl KCL Spacer
	0525	1	11-7					Plug RH + MH [30-20]
	0530	4 1/2	28 29		✓			Mix 80 sks of SMP @ 12.7 ppg
		4 1/2	24		✓			Mix 100 sks of EA-2 @ 15.36 ppg
	0555							Wash P+L Drop Latch down Plug
	0600	6 1/2	0		✓	250		Start Displacement
		6 1/2	75		✓	350		-Lift Pressure
		6 1/2	109		✓	800		-Max Lift Pressure
	0615	5 1/2	110		✓	1600		Land Latch down Plug Release Pressure * Hold *
	0620							Wash up Trk #112
	0650							Job Complete
								130 sks of SMD + 100 sks of EA-2 used
								Thank You,
								Gideon Preston, Kurlby