

WF
Job Log

Customer:	Berexco LLC	Cement Pump No.:	38750, 19919 7.5Hrs.	Operator TRK No.:	96816	
Address:	2020 N Bramblewood	Ticket #:	1718 19817 L	Bulk TRK No.:	33021, 37724 Corey	37712, 19883 Oscar
City, State, Zip:	Wichita Ks 672016	Job Type:	Z-42 Cement Surface Casing			
Service District:	1718 - Liberal, Ks.	Well Type:	OIL			
Well Name and No.:	Risa # 1-22	Well Location:	22-30S-33W	County:	Haskell	State: Kansas

Type of Cmt		Sacks	Additives		Truck Loaded On				
A Serv Lite		580	3% Calcium Chloride, 1/4# Polyflake		33021, 37724 Corey		Front Back		
Class C		150	2% Calcium Chloride, 1/4# Polyflake		37712, 19883 Oscar		Front Back		
							Front Back		
Lead/Tail:		Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel			
Lead:		12.5	1.98	10.77	1148.4	TT Man Hours:	31		
Tail:		14.8	1.34	6.33	201	# of Men on Job:	4		
Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials		
			T	C	Tubing	Casing			
11:30							ON LOCATION & SAFETY MEETING		
13:00							RIG UP		
2:25 PM							RIG TO CIRCULATE		
3:10 PM							RIG TO PT		
3:16 PM							PRESSURE TEST TO 3300PSI		
15:18	5	196.2 slurry				120	PUMP 580SX LEAD @ 12.5#		
16:00	5	35.7 slurry				170	PUMP 150SX TAIL @ 14.8#		
4:09 PM							SHUTDOWN / DROP PLUG		
16:11	3.6	10				100	DISPLACE		
	5	20				130			
16:19	5	30				180	CEMENT RETURNS @ 35BBL IN, 5BPM @ 190PSI		
	5	40				200			
	5	50				250			
	5	60				280			
	5	70				360			
	5	80				410			
16:30	5	85				440	SLOW RATE TO 2.0BPM @ 350PSI		
	2	90				370			
	2	100				430			
16:41	2	105.9				460	LAND PLUG / PRESSURE UP TO 750PSI		
							RELEASE BACK --- FLOAT HELD		
							JOB COMPLETE		
							APRROX. 276SX, 70.9BBLS		
Size Hole	12 1/4"	Depth	1720'			TYPE	Plug Container		
Size & Wt. Csg.	8 5/8" 24#	Depth	1708.07'	New / Used		Packer	Depth		
Landing Press.	409.1psi	Depth				Retainer	Depth		
Shoe Jt.	42.24'	Type				Perfs	CIBP		
Customer Signature:						Basic Representative:		Daniel Beck	
						Basic Signature:			
						Date of Service:		11/11/2019	

Berexco LLC
Risa #1-22

