



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	Merit Energy	Cement Pump No.:	38119-19570 5 HRS	Operator TRK No.:	96815
Address:	sublette.invoice@meritenergy.com	Ticket #:	1718-19745 L	Bulk TRK No.:	30463-37547
City, State, Zip:	PO Box L, Sublette, Ks. 67877	Job Type:	Z-42 Cement Production Casing		
Service District:		Well Type:	OIL		
Well Name and No.:	Lester # 1 AFE # 64451	Well Location:	33-27S-34W	County:	Haskell
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
50/50 POZ	305	6%GYPSUM, 10%SALT, 1/4#DEFOAMER, 5#GILSONITE, 1/4#POLYFLAKE	30463-37547	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	13.6#	1.57	7.18	478.85	Man Hours:	24
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
17:30							ON LOC, SAFTEY MTG, R.U.
20:45						3000	TEST LINES
8:47 PM	5.5	10				400	PUMP MUD FLUSH
8:50 AM	5 5	5				440	H2O SPACER
8:56 PM							PLUG RAT AND MOUSE
21:06	5.8					340	START MIXING @ 13.6#
21:26		71.5					SHUT DOWN, DROP PLUG, WASHUP
9:35 PM	7					100	START DISPLACEMENT 4%KCL
21:57	2.5	115				1070	SLOW RATE
22:03		129				1340-1700	PLUG DOWN
22:08							RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	7 7/8	Depth	5610'		TYPE	
Size & Wt. Csg.	5 1/2 17	Depth	5610'	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Top Plugs		Type			Perfs	CIBP

Customer Signature:	Basic Representative:	CHAD HINZ
	Basic Signature:	
	Date of Service:	9/28/2019

MERIT
LESTER 1

